This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`



THE GIFT OF
Sheehan Bk. Company

College, London.

No. 19.—STRENGTH OF BEAMS UNDER TRANSVERSE LOADS. By Prof. W. Allan, author of "Theory of Arches." Second edition, revised.

No. 20.—BRIDGE AND TUNNEL CENTRES. By John B. McMaster, C.E. Second edition.

No. 21.—SAFETY VALVES. Second Edition. By Richard H. Buel, C.E.

No. 22.—HIGH MASONRY DAMS. By E. Sherman Gould, M. Am. Soc. C. E.

No. 23.—THE FATIGUE OF METALS UNDER REPEATED STRAINS. With various Tables of Results and Experiments. From the German of Prof. Ludwig Spangenburgh, with a Preface by S. H. Shreve, A.M.

No. 24.—A PRACTICAL TREATISE ON THE TEETH OF WHEELS. By Prof. S. W. Robinson. Second edition, revised.

No. 25.—ON THE THEORY AND CALCULATION OF CONTINUOUS BRIDGES. By Mansfield Merriman, Ph.D.

No. 26.—PRACTICAL TREATISE ON THE PROPERTIES OF CONTINUOUS BRIDGES. By Charles Bender, C.E.

No. 27.—ON BOILER INCRUSTATION AND CORROSION. By F. J. Rowan. New Ed. Rev. by F. E. Idell.

No. 28.—TRANSMISSION OF POWER BY WIRE ROPES. Second edition. By Albert W. Stahl, U.S.N.

No. 29.—STEAM INJECTORS. Translated from the French of M. Leon Pochet.

No. 30.—TERRESTRIAL MAGNETISM AND THE MAGNETISM OF IRON VESSELS. By Prof. Fairman Rogers.

No. 31.—THE SANITARY CONDITION OF DWELLING-HOUSES IN TOWN AND COUNTRY. By George E. Waring, jun.

No. 32.—CABLE-MAKING FOR SUSPENSION BRIDGES. By W. Hildebrand, C.E.

No. 33.—MECHANICS OF VENTILATION. By George W. Rafter, C.E. New and Revised Edition.

No. 34.—FOUNDATIONS. By Prof. Jules Gaudard, C.E. Second edition. Translated from the French.

No. 35.—THE ANEROID BAROMETER: ITS CONSTRUCTION AND USE. Compiled by George W. Plympton. Fourth edition.

No. 36.—MATTER AND MOTION. By J. Clerk Maxwell, M.A. Second American edition.

No. 37.—GEOGRAPHICAL SURVEYING; ITS USES, METHODS, AND RESULTS. By Frank De Yeaux Carpenter, C.E.

No. 38.—MAXIMUM STRESSES IN FRAMED BRIDGES. By Prof. William Cain, A.M., C.E. New and revised edition.

No. 39.—A HANDBOOK OF THE ELECTRO-MAGNETIC TELEGRAPH. By A. E. Loring.

No. 40.—TRANSMISSION OF POWER BY COMPRESSED AIR. By Robert Zahner, M.E. Second edition.

No. 41.—STRENGTH OF MATERIALS. By William Kent, C.E. Second Edition.

No. 42.—VOUSSOIR ARCHES APPLIED TO STONE BRIDGES, TUNNELS, CULVERTS, AND DOMES. By Prof. William Cain.

No. 43.—WAVE AND VORTEX MOTION. By Dr. Thomas Craig, of Johns Hopkins University.

No. 44.—TURBINE WHEELS. By Prof. W. P. Trowbridge, Columbia College. Second edition. Revised.

No. 45.—THERMODYNAMICS. By Prof. H. T. Eddy, University of Cincinnati.

No. 46.—ICE-MAKING MACHINES. From the French of M. Le Doux. Revised by Prof. Denton.

No. 47.—LINKAGES; THE DIFFERENT FORMS AND USES OF ARTICULATED LINKS. By J. D. C. de Roos.

No. 48.—THEORY OF SOLID AND BRACED ARCHES By William Cain, C.E.

No. 49.—ON THE MOTION OF A SOLID IN A FLUID. By Thomas Craig, Ph.D.

No. 50.—DWELLING-HOUSES: THEIR SANITARY CONSTRUCTION AND ARRANGEMENTS. By Prof. W. H. Corfield.

No. 51.—THE TELESCOPE: ITS CONSTRUCTION, ETC. By Thomas Nolan.

No. 52.—IMAGINARY QUANTITIES. Translated from the French of M. Argand. By Prof. Hardy.

No. 53.—INDUCTION COILS: HOW MADE AND HOW USED. Fifth edition.

No. 54.—KINEMATICS OF MACHINERY. By Prof. Kennedy. With an introduction by Prof. R. H. Thurston.

No. 55.—SEWER GASES: THEIR NATURE AND ORIGIN. By A. de Varona. 2d ed., revised and enlarged.

No. 56.—THE ACTUAL LATERAL PRESSURE OF EARTHWORK. By Benjamin Baker, M. Inst. C.E.

No. 57.—INCANDESCENT ELECTRIC LIGHTING. A Practical Description of the Edison System. By L. H. Latimer, to which is added the Design and Operation of Incandescent Stations. By C. J. Field, and the Maximum Efficiency of Incandescent Lamps, by John W. Howell.

No. 58.—THE VENTILATION OF COAL-MINES. By W. Fairley, M.E., F.S.S., and Geo. J. André.

No. 59.—RAILROAD ECONOMICS; OR, NOTES, WITH COMMENTS. By S. W. Robinson, C.E.

Engineering
Library
TG
329
.H99
1899
cop. 2

SKEW ARCHES.

ADVANTAGES AND DISADVANTAGES

OF

DIFFERENT METHODS

OF CONSTRUCTION.

BY

E. W. HYDE, C. E.

NEW YORK:

D. VAN NOSTRAND CO., PUBLISHERS,

23 MURRAY AND 27 WARREN STREETS.

1899.

012-31-18 8/11

PREFACE.

The author was led to make the investigations contained in this little treatise by a desire to satisfy his own mind as to the relative advantages of several different methods which have been employed in the construction of Skew Arches.

The two important points of comparison that naturally suggest themselves to the investigator are:

1st. Relative security;

2d. Relative facility of construction.

A discussion and comparison of three modes of construction, with special reference to these points, will be found in the following pages, together with brief descriptions of the manner of making the necessary draughts, patterns, templets, etc.

The paper first appeared in VAN NOSTRAND'S ENGINEERING MAGAZINE, for which it was written.

E. W. HYDE.

Reference 2-1-42 MgZ

31[illegible]

PREFACE

TO SECOND EDITION.

As the demand for this little treatise had exhausted the first edition, a new one was plainly suggested.

Although strictly technical in its character, and belonging to the less frequented field of practical engineering, it manifestly supplied a want.

The present issue, except for a few typographical corrections is a literal reprint, of the first edition.

G. W. P.

Jan. 1900.

SKEW ARCHES.

I PROPOSE in this paper to discuss to some extent three methods which have been employed in the construction of oblique or skew arches, and to make a comparison of their relative security, facility of construction, etc.

The three methods will be designated as,

1st. The Helicoidal method.

2d. The Logarithmic method.

3d. The "Corne de Vache" or Cow's-horn method.

The first two names are derived from the nature of the coursing and heading, joint surfaces and their intersections with the soffit, and the third from the soffit itself, which is a warped surface that has been thus named. They will be considered in the order given above.

The following abbreviations will be used throughout the paper:

C j c, for coursing joint curve, or intersection of coursing joint with soffit.

H j c, for heading joint curve.

C j s, for coursing joint surface.

H j s, for heading joint surface.

H P, for the horizontal plane of projection.

V P, for the vertical plane of projection.

P F, for the plane of the face of the arch.

Ex. s, for the extradosal or outer surface of the arch.

THE HELICOIDAL METHOD.

In this method the C j s's and H j s's are both warped helicoids, and of course their intersections with the soffit helices.

Let C D D_2 C_2 be the projection of the soffit on the H P which coincides with the springing plane of the arch, and D′ V C_2 is a semicircle whose radius will be designated by *r*.

The Ex. s will be taken as a concentric cylinder projected in A B B_2 H_2 and B' V' A_2 and its radius will be designated by r_1.

To construct the C and H j c's we will first develop the soffit. Lay off $O_1 T = \pi = 3{,}1416\ r$; the points of the curve D E F C_1 may be found by the principles of descriptive geometry or by means of the equation of the curve, which we shall obtain. The latter method is much more accurate for construction upon a large scale.

Let $h = D'\ D_2$, and α = angle $C\ D_2\ D' =$ obliquity of the arch; $\therefore$ tang. $\alpha = \frac{2r}{h}$.

Also θ = variable angle $s\ Q\ D'$. The origin will be taken first at O_1. We have from the figure

$O_1\ \beta = x = r\ \theta.$

$O\ y = \frac{1}{2}\ h$, E $\beta = -\ y.$

$$\therefore \frac{\frac{1}{2}h + y}{h} = \frac{r\ (1 - cos\ \theta)}{2r} = \frac{1 - cos\ \theta}{2}$$

$$\therefore \quad 1 - cos\ \theta = \frac{h + 2y}{h}$$

and $\cos\theta = -\frac{2y}{h}$

$$\therefore \quad \theta = \cos^{-1}\left(-\frac{2y}{h}\right)$$

whence $x = r\cos^{-1}\left(-\frac{2y}{h}\right)$.

Solving for y we have

(1) $$y = -\frac{h}{2}\cos\frac{x}{r},$$

which is the equation of D E F C, with the origin at O_1. If the origin be moved to O_2 the equation becomes

(2) $$y = \frac{h}{2}\sin\frac{x}{r}.$$

From either of these equations the values of y for given values of x may be easily obtained by the aid of a table of natural sines and cosines.

Having constructed the curve D E F C_1, join D and C_1 by a straight line. This will be the development of a H j c. At O_2 draw O_2 S perpendicular to D C_1. O_2 S is the development of ¼ of a spire of the

helix which forms the C j e's, and corresponds to the curve O P R.

The angle $T O_1 S = T C_1 O_2 = tang.—^1 \frac{\pi r}{}$

$$\therefore TS = O_2 T \ tang \ TO_2 S = \frac{\pi^2 r^2}{2h} = \tfrac{1}{4} \pi^2 r \ tan \ \alpha \quad (3)$$

Now divide D E F C_1 into a convenient odd number of equal parts, so arranging it as to cause one of the C j c's as δ D_2 to pass through D_2. The developments of the C j c's are of course drawn parallel to O_2 S through the points of division of the curve D E F C_1. If it were not convenient to divide D E F C_1 in such a manner that a line through D_2 parallel to O_2 S would exactly pass through one of the points of division, the direction of the C j c's might be slightly changed, or the divisions between D_2 δ and C_2 δ might be made very slightly larger or smaller, as the case required, then the divisions from D to δ and from C_2 to δ'. The latter method seems preferable, since it preserves the perpendicularity between the C and H j c's, and the difference in the

size of the voussoirs would be so small as not to be noticeable.

All the courses below δ and δ_1 run out into the abutment, and the impost must be cut in steps, as shown in the figure, into which the voussoirs will fit.

A G H B_1 is the development of the extrados, and the right line $x\ y$ that of a helix in which one of the H j s's intersects the Ex. s. O_4 R_1 is the development of the curve O L R_1, in which a C j s intersects the Ex. s.

$$Tan\ x\ y\ O_3 = \frac{h}{\pi r_1}.$$

$$Tan\ O_3\ O_4\ R = \frac{T\ S}{\frac{1}{2}\pi\ r_1} = \frac{\pi^2\ r^2}{2\ h} \div \frac{\pi\ r_1}{2} =$$

$$\frac{r}{r_1},\ \frac{\pi\ r}{h} = \frac{\pi\ r}{2\ r_1}\ tan\ \alpha.$$

The C j s's are generated by a right line moving on the axis O Q as one directrix, the helix O P R as a second, and remaining always perpendicular to the former. Hence the V P is a plane director of the surface.

The details of the construction of a skew arch by this method are fully developed in "A Practical and Theoretical Essay on Oblique Bridges," by John Watson Buck, M. Inst. C. E. He, however, makes the C and H j s's *hyperbolic paraboloids* instead of helicoids, as follows: The corners of the voussoirs are normals to the soffit at the intersection of the H and C j c's, and hence are elements of the warped helicoids, which *should* form the H and C j s's. The points where two of the normals on the same side of the voussoir pierce the soffit are joined by a right line, and this line is moved on the normals as directrices in such a manner as to pass over equal distances, measured on the normals in equal times, by which operation a hyperbolic paraboloid is generated. The accompanying figure is an exaggerated representation of the effect of cutting the stones in this manner. A B C D and E F G H are the developed introdosal surfaces of two voussoirs in successive courses. If the courses were not required to break

joints, the stones would fit perfectly, but as this is necessary to the stability of the arch, that portion of a stone which is too



full will come opposite to the portion of the one in the next course which is likewise too full, and similarly the hollow portion

of one opposite to the hollow portion of the next.

The truth of these statements will appear as follows: The hyperbolic paraboloid evidently cannot coincide with the helicoid, as they are surfaces constructed according to a different law. The normals to the two adjacent corners of a voussoir are elements of both surfaces. The normal midway between these two is also an element common to the two surfaces. Hence it is evident from the mode of their generation that the two surfaces intersect each other along each of these three lines. A section of the surfaces by a plane perpendicular to the middle normal would give something like the accompanying figure, the straight line being the intersection with the hyperbolic paraboloid and the curve that with the helicoid.

However, if the voussoirs are small compared with the whole arch, as in Fig. 1, the difference between the paraboloidal

and helicoidal surfaces in the length of one voussoir will be exceedingly small, and the stones will fit with sufficient exactness for practical purposes. Nevertheless, the *tendency* is to cause the pressure to be unequally distributed, concentrating it at K, K_1, K_2 and at A, C, E and G. The difficulty of cutting the warped faces of the voussoirs is considerably diminished by this approximate method.

An investigation will now be made of the security of an arch constructed according to the helicoidal method.

In order that there may be *no* tendency in the successive courses to slide upon each other, it is evident that each C j s must be at every point normal to the direction of the pressure at that point. We shall consider first the direction of pressure as regards its parallelism to a certain vertical plane, without reference to the angle it may make at any point with the H P. This vertical plane is the place of the face of the arch. It is probable that the direction of pressure varies somewhat with reference to this plane in differ-

ent portions of the arch, especially if the crown settles to any extent after removal of the centre. Still it must be approximately parallel to the P F, otherwise the portions near B and A_2 would be unsupported and would consequently fall. For the purposes of the investigation then the direction of pressure will be *assumed* to be in a plane parallel to the P F, and from the results obtained we shall be able to see without difficulty the effect upon the security of the arch which would be produced if the direction of pressure were *not* parallel to the P F. Proceeding then on this assumption, a line drawn on the C j s of any voussoir and lying in a plane perpendicular to the P F and to the H P *ought* to be *horizontal*, but as this line would be the intersection of a warped helicoid by a plane not containing an element of the surface, it must be a *curve*, and can only be horizontal at a maximum or a minimum point, at infinity, or at some singular point. The intersection of the C j s of a voussoir by a *horizontal* plane should give a line

perpendicular to the P F, but this line would be also a curve, and could have the required direction only at one or more points. It becomes necessary then to discover the nature of these curves and the direction of their tangents at the point of piercing the soffit.

In Fig. 1 (Frontispiece) the curves Q P'_4 *a*, Q P'_3 *b*, etc., are the vertical projections of the curves cut by the vertical planes, P_4 *c*, P_3 *k*, etc., from the helicoid whose directrices are the axis O Q and the helix O P R. The curve Q P′*c* has a maximum point at P P′ where it pierces the soffit; all those above it have a maximum point *outside* the soffit, and those below it have one *inside* the same.

The curves O P_4 *r*, O P_3 *q*, etc., are cut by horizontal planes through the points P_4 P'_4 P_3', etc. The curve through P is not drawn, but if it were it would be tangent at P to the line P *h*.

It is plain from inspection of these curves that the courses below P P′ have a tendency to slide upon each other in a direction from A_3 towards A, which increases as the

abutment is approached. In Fig. 1 this point P P′ is on the tenth course from the abutment, and there are three coursing joints which would have a tendency to slide throughout their whole length with nothing to resist it except friction between the surfaces. The *partial* courses would be prevented from sliding by the steps cut in the impost. Above P P′ the tendency to slide would be in the opposite direction, but would be so small as not to affect seriously the stability of the arch. This will be evident from inspection of the curves O P_1 *p* and O P_2 *o*.

We will now investigate these curves analytically and determine the position of the point P P′.

The distance T S, Fig. 1, is ¼ the height of one spire of the helix O P R, and

from eq. (3) $TS = \frac{\pi^2 r^2}{2h} = \frac{1}{4}\pi^2 r \tan \alpha.$

Call the height of one spire of the helix h_1, then

$$h_1 = \frac{2\pi^2 r^2}{h} = \pi^2 r \tan \alpha.$$

Let O be the origin of coörds, the axis of the cylinder, O Q, the axis of z, O T the axis of x, and the axis of y a vertical line through O. Then we shall have for the helix O P R,

$$\frac{\theta - \frac{\pi}{2}}{2\pi} = \frac{z}{h_1};$$

whence $\theta = \frac{2\pi z}{h_1} + \frac{\pi}{2}$.

Also

$$x = r \cos\theta = r \cos\left(\frac{2\pi z}{h_1} + \frac{\pi}{2}\right) = -r \sin\frac{2\pi z}{h_1},$$

or substituting for h, its value

$$(4) \qquad x = -r \sin\frac{h z}{\pi r^2}$$

which is the equation of O P R, the projection on X Z of one of the C j c's. The vertical projection, or the projection on X Y of this helix is

$$(5) \qquad x^2 + y^2 = r^2.$$

To obtain the equation of the C j s, we

must find the equations of an element, and then eliminate the constant which fixes its position. Let one equation of the element be

$$z = z_1. \tag{6}$$

To find the equation in terms of x and y, substitute in the equation

$$\frac{y - y_1}{x - x_1} = \frac{y_1 - y_2}{x_1 - x_2}$$

of a line through two points the proper values of x_1, x_2, y_1 and y_2. We have since all the elements cut the axis of z,

$$x_1 = o \text{ and } y_1 = o.$$

Substituting from (6) in (4)

$$x_2 = -r \sin \frac{h z_1}{\pi r_1},$$

and substituting this value of x_2 in (5),

$$y_2 = \sqrt{r^2 - r^2 \sin^2 \frac{h z_1}{\pi r^2}} = r \sqrt{1 - \sin^2 \frac{h z_1}{\pi r^2}}$$

$$= r \cos \frac{h z_1}{\pi r^2}.$$

$$\therefore \frac{y}{x} = - \frac{r \cos \frac{h z_1}{\pi r^2}}{r \sin \frac{h z_1}{\pi r^2}} = - \cot \frac{h z_1}{\pi r^2};$$

or making z_1 general by dropping the subscript,

$$(7) \qquad y = - x \cot \frac{h z}{\pi r^2},$$

which is the equation of a C j s.

Now, intersect this surface by a vertical plane perpendicular to the P F, whose equation is

$$(8) \qquad z = \frac{2 r}{h} (a_1 - x),$$

in which a_1 is the intercept on X.

$$(9) \qquad \therefore y = - x \cot \left(\frac{2 (a_1 - x)}{\pi r} \right)$$

which is the equation of the curves Q P′ c, etc.

In equation (9) if

$$x = 0, \qquad y = 0;$$

if $x = a_1 - \frac{(2 n - 1) \pi^2 r}{4}$,

$$y = -x \cot \frac{(2n-1)\pi}{2} = 0,$$

n being an integer;

$$\text{if } x = a_1 - \frac{n\pi^2 r}{2},$$

$$y = -x \cot n\pi = \infty,$$

n as before being an integer. Hence the curve has an infinite number of branches. It is to be noticed that equation (9) *does not contain* h, the only constants being π, a_1 and r, *hence the form of the curves* $Q\ P'\ c$, $Q\ P_1'\ d$, etc., *is entirely independent of the obliquity of the arch.* We will next differentiate equation (9) for a maximum.

$$\frac{dy}{dx} = -\cos\left(\frac{2(a_1-x)}{\pi r}\right) - \frac{2x}{\pi r \sin^2\left(\frac{2(a_1-x)}{\pi r}\right)}$$

Let $\frac{2(a_1-x)}{\pi r} = u$

$$(10) \quad \therefore \quad \frac{dy}{dx} = -\cot u - \frac{2x}{\pi r \sin^2 u}$$

For a maximum

$$\cot u = -\frac{2x}{\pi r \sin^2 u}.$$

$$(11)\ \therefore x_{ymax} = -\frac{\pi r \sin u \cos u}{2}$$

By solving equation (11) the values of x for which y is a maximum or minimum can be obtained. It is only capable, however, of an approximate solution, but if we obtain the x co-ordinate of the intersection of the locus of equation (9) with the circle

$$(12) \qquad x^2 + y^2 = r_2^2,$$

in which r_2 may have any value, and place this value of x equal to that in equation (11), we shall obtain the value of x_{ymax} when the maximum point is at the intersection of the two curves.

$\therefore$ substituting from (9) in (12)

$$x_i^2 + x_i^2 \cot^2 u_i = r_2^2$$

$$x_i^2 (1 + \cot^2 u_i) = x_i \operatorname{cosec}^2 u_i = r_2^2.$$

$$(13 \qquad \therefore \quad x_i = r_2 \sin u_i.$$

$\therefore$ by (11) and (13),

$$r_2 \sin u_i = -\frac{\pi r \sin u_i \cos u_i}{2}$$

$$\therefore \cos u_i = -\frac{2 r_2}{\pi r}$$

$$\frac{2\,(a_1 - x_1)}{\pi\, r} = u_i = \cos^{-1}\left(-\frac{2\,r_2}{\pi\, r}\right)$$

$$\therefore\ x_i = a_1 - \frac{\pi\, r}{2}\cos^{-1}\left(\frac{2\,r_2}{\pi\, r}\right).$$

Denoting by x_{mi} the value of x_i for which y is a maximum when the locus of (9) is subject to the condition of having a maximum point at its intersection with $x^2 + y^2 = r_2^2$, and substituting the value of x just found in the 2d member of (13), we have

$$x_{mi} = r_2 \sin\left\{\frac{\left(2a_1 - a_1 + \frac{\pi\, r}{2}\cos^{-1}\left(-\frac{2r_2}{\pi\, r}\right)\right)}{\pi\, r}\right\}$$

$$= r_2 \sin\cos^{-1}\left(\frac{2\,r_2}{\pi\, r}\right)$$

$$= r_2 \sin\sin^{-1}\sqrt{1 - \frac{4\,r_2^2}{\pi^2 r^2}}$$

$$= r_2\,\frac{\sqrt{\pi^2 r^2 - 4\,r_2^2}}{\pi^2 r^2}$$

(14) $$\therefore\ x_{mi} = r_2\,\frac{\sqrt{\pi^2 r^2 - 4\,r_2^2}}{\pi\, r}$$

Let $r_2 = r$, this being the condition that the maximum point shall be at the point where the locus of (9) pierces the soffit, and we have

$$(15) \quad x_{ml} = \frac{r}{\pi} \sqrt{\pi^2 - 4} = r \cos \tau.$$

Whence

$$(16) \quad x_{ml} = 0.77118r = r \cos 39^\circ\ 32'\ 23''.$$

This value of τ may also be found by means of the curves OP_1p, OP_2o, etc. Intersect the surface of equation (7) by the horizontal plane

$$(17) \qquad y = b.$$

$$\therefore\ b = -\ x \cot \frac{h\,z}{\pi\, r^2}$$

$$(18) \quad \text{or} \quad x = -b \tan \frac{h\,z}{\pi\, r^2},$$

the equation of the curves OP_1p, etc.

Differentiating

$$(19) \quad \frac{dz}{dx} = -\ \frac{\pi\, r^2}{b\, h} \cos^2 \frac{h\,z}{\pi\, r^2}$$

If $z = \pm \frac{\pi^2\, r^2}{2\, h}$ in (18) and (19) we have

$$x = \infty, \text{ and } \frac{dz}{dx} = o,$$

showing that the lines $z = \pm \frac{\pi^2 r^2}{2h}$ are asymptotes of the curves.

Intersect the circle $x^2 + y^2 = r_2^2$ by $y = b$.

$$\therefore \quad x_i = \pm \sqrt{r_2^2 - b^2}.$$

Substitute this value of x in (18) and

$$\pm_1 \sqrt{r_2^2 - b^2} = -b \tan \frac{h z_i}{\pi r^2}, \text{ whence}$$

$$(20) \quad z_1 = \frac{\pi r^2}{h} \tan^{-1}\left(\frac{\pm \sqrt{r_2^2 - b^2}}{b}\right)$$

z_i is the z co-ordinate of the point in which the locus of (18) pierces the cylinder, concentric with the soffit, whose radius is r_2.

Substitute from (20) in (19), thus

$$\frac{dz_i}{dx_i} = -\frac{\pi r^2}{b h} \cos^2 \left\{ \tan^{-1}\left(\frac{\pm\sqrt{r_2^2 - b^2}}{b}\right) \right\}$$

$$= -\frac{\pi r^2}{b h} \left\{ \cos \cos^{-1} \frac{1}{\sqrt{1 + \frac{r_2^2 - b^2}{b^2}}} \right\}^2$$

$$(21) \qquad = -\frac{\pi\, b}{h}\left(\frac{r}{r_2}\right)^2$$

If $r_2 = r$, when the cylinder mentioned above becomes the soffit,

$$(22) \qquad \frac{dz_i}{dx_i} = -\frac{\pi\, b}{h},$$

which is the tangent of the angle between the tangent to the locus of (18) and the axis of x at the point where the locus pierces the soffit. If we make the condition that

$$(23) \qquad \frac{dz_i}{dx_i} = -\frac{2\, r}{h},$$

that is, that the tangent at this point shall be perpendicular to the P F, we have from (22) and (23)

$$\frac{\pi\, b_1}{h} = \frac{2\, r}{h}$$

$$(24) \quad \therefore b_1 = \frac{2\, r}{\pi} = 0.63662\, r = r \sin 39^\circ 32' 23''$$

which agrees with equation (16).

It is thus apparent that in an arch constructed by this method the portions below PP′ or beyond the line $\eta\gamma$ on the

development, should be *omitted; i. e.*, the arch should be *always segmental* with a span not exceeding

$$2\,r\cos\tau = 2\,r\cos 39^\circ\,32'\,23'' = 1.54236r,$$

provided that there is to be no tendency in the successive courses to slide on one another. The amount of this tendency to slide and its relation to the obliquity of the arch will next be investigated.

Let us obtain an expression for the angle $\zeta\,P_4\,\mu$ between the tangent line to O $P_4\,r$ at P_4 and the line $P_4\,\zeta$ perpendicular to the P F. Let $\zeta\,P_4\,\mu = \theta'$ then, equation (22),

$$\theta' = tan^{-1}\frac{2\,r}{h} - tan^{-1}\frac{\pi\,b}{h}$$

$$\therefore\ tan\,\theta' = \left(tan^{-1}\frac{2\,r}{h} - tan^{-1}\frac{\pi\,b}{h}\right) = \tag{25}$$

$$\frac{\frac{2\,r}{h} - \frac{\pi\,b}{h}}{1 + \frac{2\,\pi\,b\,r}{h^2}} = \frac{h\,(2\,r - \pi\,b)}{h^2 + 2\,\pi\,b\,r}$$

If $h = o$, $tan\,\theta' = o$, $\therefore\ \theta' = o$.
If $h = \infty$ $tan\,\theta' = o$, $\therefore\ \theta' = o$.

θ' must be equal to θ when $tan\ \theta' = \phi$ because it can never equal, much less exceed 90°; for if it *can* equal 90°, then we must have from (25)

$$h^2 + 2\,\pi\,b\,r = 0$$
$$\therefore h = \sqrt{-2\,\pi\,b\,r};$$

i. e., h must be imaginary. It follows that there must be some value of h for which tan θ' and therefore θ', is a maximum. By placing the first differential co-officient of the function with reference to $h=o$, we find this value to be

$$(26). \qquad h = \sqrt{2\,\pi\,b\,r}.$$

By this equation $h = 2\,r\ cot\ \alpha = 1.0445\,r$,

$$\theta'^{\max} \qquad \theta'^{\max}$$

when $b = r\ sin\ 10° \therefore \alpha = 62°\ 25'$ for

$$\theta'^{\max}$$

this value of b.

Now the tendency to slide at any point, as $P_4\ P_4'$, depends upon the angle between the normal to the C j s at that point and the direction of the pressure. This last we have assumed to be in a plane parallel to the P F. We will now

assume for the purposes of the investigation that it coincides at the point P_4P_4' with the direction of the tangent at that point to the ellipse cut from the soffit by a plane through the point parallel to the P F. Let p_1 = tangent of angle between ground line and tangent line to curve Q P_4' a at the point P_4'; then the tangent of the angle between the tan line to this curve in space at the point P_4P_4' and the H P will be $= p_1 \cos \alpha$.

Let p_2 = tangent of angle between a vertical line and the tangent line to the circle D′ V C_2 at the point P_4' = angle P_4' Q C_2, then the tangent of the angle between a vertical and the tangent line at P_4 P_4' to the section of the soffit parallel to the P F will be $= p_2$ cosec α.

Now to find the angle between the normal at P_4 P_4' to the C j s, and the tangent to the section parallel to the P F, we have given two sides and the included angle of a sperical triangle, the included angle being θ'.

Let N = angle between normal to

C j s, at P_4 P_4' and vertical = angle be



tween tangent plane to C j s at P_4 P_4' an H P, then we find the value of tan N to be tan N $= p_1 \cos \alpha \operatorname{cosec} \theta'$.

$$(27) \quad \therefore \sin N = \frac{p_1 \cos \alpha \operatorname{cosec} \theta'}{\sqrt{1 + p_1^2 \cos^2 \alpha \operatorname{cosec}_2 \theta'}}$$

$$(28) \quad \cos N = \frac{1}{\sqrt{1 + p_1^2 \cos^2 \alpha \operatorname{cosec}^2 \theta'}}$$

and if $t_e = \tan^{-1}(p_2 \operatorname{cosec} \alpha)$, we have

$$(29) \quad \sin t_e = \frac{p_2 \operatorname{cosec} \alpha}{\sqrt{1 + p_2^2 \operatorname{cosec}^2 \alpha}}$$

$$(30) \quad \cos t_e = \frac{1}{\sqrt{1 + p_2^2 \operatorname{cosec}^2 \alpha.}}$$

By spherical trigonometry

(31) $\cos \Phi = \cos N \cos t_0 + \sin N \sin t_0 \cos \theta'$; whence, by substituion

(32)
$$\cos \Phi = \frac{1 + p_1 p^2 \cot \alpha \cot \theta'}{\sqrt{(1 + p_1^2 \cos^2 \alpha \operatorname{cosec}^2 \theta')(1 + p_2^2 \operatorname{cosec}^2 \alpha)}}$$

Multiplying numerator and denominator by $\sin \alpha \sin \theta'$, this becomes

(33)
$$\cos \Phi = \frac{\sin \alpha \sin \theta' + p_1 p_2 \cos \alpha \cos \theta'}{\sqrt{\sin^2 \theta' + p_1^2 \cos^2 \alpha)(p_2^2 + \sin^2 \alpha}}$$

If in this equation $\alpha = \alpha$, by equation (25), since $h = 2 r \cot \alpha$, $\theta' = o$, and hence $\cos \Phi = \frac{p_1 p_2}{p_1 p_2} = 1, \therefore \Phi = o.$

If $\alpha = 90^0$ — *i. e.*, the obliquity $= 0$ — by (25) $\theta = 0$, and hence cos $\Phi = \frac{0}{0}$ indeterminate. The reason for this is, that the tangent lines to the curves $\mathcal{C}$ P_4, $QP_4'a$, and OP_4r, $P'_4\pi$ by which we have fixed the position of the tangent plane

coincide when $\alpha = 90^0$. The value towards which cos Φ *approaches*, however, is unity, as α approaches 90^0, for from the relations between the quantities it is evident that when $\theta' = 0$, N must equal t_e, and hence by equation (31),

$$\cos \Phi = \cos^2 t_e + \sin^2 t_e = 1; \quad \therefore \quad \Phi = o.$$

It follows, therefore, that there must be some value of α for which cos Φ is a minimum, and therefore Φ a maximum, for any given values of p_1 and p_2. Owing to the complexity of the expression for cos Φ, this value would be very difficult to obtain by differentiation; but it can be determined approximately by calculating a series of values of cos Φ for different values of α. This has been done, with the following results:

The point for which the calculations are made is $P_4\ P_4'$, for which

$x = -r \cos 10°$, $y = b = r \sin 10°$, $z = \frac{4\pi^2 r^2}{9h} p_2 = \tan 10°$, and $p_1 = 0.47011 = \tan 25°\ 10'\ 43''$, the value of p_1 being found by equation (10).

TABLE I.

When $\alpha = 60°, \theta' = 34° 42' 41''$, and $\Phi = 14° 57' 30''$

" $\alpha = 40°, \theta' = 27° 10' 00''$, " $\Phi = 25° 27' 00''$

" $\alpha = 30°, \theta' = 21° 3' 00''$, " $\Phi = 31° 00' 00''$

" $\alpha = 20°, \theta' = 14° 19' 50''$, " $\Phi = 34° 44' 00''$

" $\alpha = 10°, \theta' = 7° 14' 50''$, " $\Phi = 29° 57' 00''$

From this table it appears that Φ is a maximum when α has some value not far from 20°.

If the point considered be P P′ for which $x = r \cos \tau = r \cos 39° 32' 23''$, and

$$y = b = r \sin 39° 32' 23'',$$

we have $\theta' = o$ and $p_1 = o_1$ $\therefore$ in equation (33) $\cos \Phi = \frac{o}{o}$, and from the same considerations as when $\alpha = 90°$, we find

$$\cos \Phi = 1, \text{ whence } \Phi = o,$$

without reference to what the value of α may be.

If, as is very probably the case, the direction of pressure is *not* exactly parallel to the P F, but inclines somewhat towards the plane of the right section of the soffit, the effect will be to *increase* the tendency to slide on the C j s's. Near the springing plane, however, the direction of pressure in a vertical plane will not be exactly parallel to the tangent to the oblique section, but will make a *less* angle with the H P, which will tend, especially when the obliquity is considerable, to counteract the previously mentioned effect. This refers to portions of the arch *below* P P′ for which $y = r \sin 39° 32' 23''$; *above* this, the tendency to sliding being in the *opposite direction;* if the line of pressure incline toward the plane of right section, it will

decrease this tendency, and then add to the stability of the arch. It is evident from inspection of the table of values of Φ that a *full centred* arch should not be built by this method unless with a small obliquity, and then it would need to be thoroughly supported by the spandrels.

These results differ entirely from those obtained in Chap. VII. of Buck's treatise on oblique arches already referred to; in fact, are in direct opposition to them. He derives a formula for the value τ *dependent upon the obliquity of the arch*, so that τ decreases with α, or as the obliquity increases, and infers therefrom that the safety of the arch *increases* as it becomes more obligue up to about 25°. I should state that his τ has a slightly different signification from mine. He undertakes to find the point at which the curves Q P'*c*, Q P'*d*, etc., cut the intrados and extrados at the *same height* above the H P, and calls the angle included between a radius drawn to this point of the intrados and the H P the angle τ. It will be

evident from inspection of the drawing that this would give to τ a somewhat *greater* value than I have obtained, but still *independent* of α, since the only constants in equation (9) are α_1 π, and r.

The following table taken from his book gives the values of τ obtained by Buck from his formula for certain values of α, from which he derives his inferences with reference to the security of oblique arches.

TABLE FROM BUCK'S ESSAY ON OBLIQUE BRIDGES.

When $\alpha = 65°$, then $\tau = 27° 17'$
" $\alpha = 55°$, " $\tau = 25° 13'$
" $\alpha = 45°$, " $\tau = 21° 47'$
" $\alpha = 35°$, " $\tau = 15° 38'$
" $\alpha = 25° 40'$ " $\tau = 0° 0'$

Immediately under this table he remarks, "It will be observed that the last angle is given 25° 40′, at which the point τ descends to the level of the axis of the cylinder, and *the whole semicircle is safe.*" * By looking at the table of values of Φ it

* The *italics* are mine.

will be seen that, for this value of α, Φ will be about 32° or 33° at 10° above the springing plane, τ of course being 39° 32′ 23″ instead of o, and hence the arch will be anything but safe if a complete semi-cylinder.

One incorrect assumption made by Buck in his derivation of the formula for the value of τ is as follows. He says: "It may be shown that the tangent of the angle which the tangent to the intradosal spiral makes with the horizon diminishes as cos τ." He does not show it, however.



Call the above mentioned angle ψ, and the angle between the tangent to the helix at any point and axis of the cylinder β, then the true relation is

$$\sin \psi = \sin \beta \cos \tau$$

$$\tan \psi = \frac{\sin \beta \cos \tau}{\sqrt{1 - \sin^2 \beta \cos^2 \tau}}$$

In the figure suppose A P to be the horizontal projection of an element $d s$ of the helix coinciding with the tangent line D E. A′ P′ is its vertical projection; and $A_1 P_1$ its revolved position about a horizontal line in a vertical plane through P. The angle $A_1 P_1 C_1 = \psi$, and the angle $C A' P' = \tau$.

$\therefore d s \sin \psi = A_1 C_1 = A' C = A' P' \cos \tau$;
but $A' P' = d s \sin \beta$;

$$\therefore \quad \sin \psi = \sin \beta \cos \tau.$$

At the springing plane the tangent to the elliptical section parallel to the P F becomes vertical, and the value of Φ is

$$(34) \quad \tan \Phi = \frac{h}{\pi r} = \frac{2}{\pi} \cot \alpha.$$

At the crown it is

$$(35)\quad \tan \Phi = \tan \theta' = \frac{(2 - \pi)\cot \alpha}{2\cot^2 \alpha + \pi}$$

The following is a table similar to table I, giving the values of Φ at the crown and springing plane, derived from equations (34) and (35).

TABLE II.

	At the Crown.	At the Springing Plane.
When $\alpha = 60° - \Phi_c$,	$= 9°50'$	$\Phi_{sp} = 18°20'$
" $\alpha = 50° - \Phi_c$,	$= 11°53'$	$\Phi_{sp} = 28°\ 7'$
" $\alpha = 40° - \Phi_c$,	$= 12°49'$	$\Phi_{sp} = 37°11'$
" $\alpha = 30° - \Phi_c$,	$= 9°16'$	$\Phi_{sp} = 47°48'$

$\Phi_c = \theta_c'$ is a maximum by equation (26) when $\alpha = 38°\ 35'$, for which value of α we find $\theta_c = 12°\ 50'$.

At the angle $\alpha = 25°\ 40'$ — the last one given in the table extracted from Buck's work—the line which he finds to be horizontal makes an angle with the H P of a little more than 29° 51′, that being the angle between the tangent to the locus of equation (9) at the point $R_{))}$ C_s and the H P.

It will be noticed that the negative sign of Φ_c in Table II. comes from the fact that in equation (35) π is greater than 2. It indicates that the tendency to sliding is in the *opposite direction* from what it is below τ.

LOGARITHMIC METHOD.

In this method the soffit is cylindrical, as in the last, and the case considered will be that in which the right section is circular.

The heading joints are *planes* parallel to the P F, which, therefore, cut the soffit in ellipses, which are the h j c's. The c j c's are drawn on the soffit in such a manner as to cut each h j c at *right* angles.

Now the angle between any two lines of the soffit remains unchanged after the development; hence, the developed c j c's must cut the developed h j c's at right angles. Also, if two lines be perpendicular to each other, their projections on a plane parallel to one of them will be per-

pendicular; hence, if the arch be projected upon a plane parallel to the P F, the vertical projections of the c j c's will cut the ellipses which are the vertical projections of the h j c's at right angles. These principles will be used in obtaining the equations of the curves.

Let A B B_2 A_2 ,, B′ V′ A_2 be the projections of the Ex. S., and C D D_2 C_2 ,, D′ V C_2 those of the soffit. O Q is the axis of the cylinder, D C_1 C_2 D_2 is the development of the soffit to be constructed from the projections, or by means of ordinates found from equations (1) or (2).

The developed h j c's are all parallel to D E O_2 F C_1, and hence may be drawn from a pattern constructsd by means of this curve. Divide D D_2 into such a number of equal parts as will make the voussoirs of convenient size, and draw the h j c's through the points of division by the pattern. The length of one of these curves is equal to that of a semi-ellipse cut from the soffit by a P F, and is calculated by the aid of the following

formula, obtained by integrating the differential of the elliptical arc.

If S = length of semi ellipse, α = semi-major axis and e = eccentricity, then

$$(36)\quad S = \pi a\left(1-\frac{e^2}{4}-\frac{3\,e^4}{64}-\frac{5\,e^6}{768}-\text{etc.}\right)$$

The *middle* h j c, *n o*, must be next divided up into a convenient odd number of equal parts. The division is done on the middle line, in order that the two faces of the arch may be alike. We will next find the equation of the curve $k\,O_2 m$ of which the c j c's on the development of the soffit are portions.

We have already found the equation of D E F C_1, equation (1), in considering the helicoidal method. With the origin at O_1, it is

$$y = -\frac{h}{2}\cos\frac{x}{r}$$

Differentiating

$$(37)\quad \frac{dy}{dx} = \frac{h}{2\,r}\sin\frac{x}{r}$$

I $k\,O_2\,m$ cut D E O_2 F C_1 at right angles,

we must have, at the point of intersection,

$$1 + \frac{dy}{dx} \cdot \frac{dy'}{dx'} = o, \text{ or } \frac{dy'}{dx'} = - \frac{dx}{dy}$$

in which $\frac{dy'}{dx'}$ is the differential co-efficient of the curve to be found. Substitute the value of $\frac{dx}{dy}$ from equation (37).

$$\therefore \frac{dy'}{dx'} = - \frac{2r}{h \sin \frac{x}{r}},$$ or dropping the primes, since the x and y in both members of the equation refer to the same point,

$$dy = - \frac{2r}{h} \cdot \frac{dx}{\sin \frac{x}{r}}.$$

$\therefore$ Integrating

$$(38) \qquad y = - \frac{2r^2}{h} l_e \tan \frac{x}{2r} + c,$$

in which l_e signifies Naperian logarithm.

If we let $y = o$, when $x = \frac{\pi r}{2}$, this being

the condition that the curve shall pass through O_2, we have

$$o = -\frac{2r^2}{h} l_e(1) + c;$$

$$\therefore c = o, \text{ and}$$

$$(39)\quad y = -\frac{2r^2}{h} l_e \tan\frac{x}{2r}.$$

If we move the origin to O_2 by placing $x = x' + \frac{\pi r}{2}$, equation (39) becomes

$$y' = -\frac{2r^2}{h} l_e \tan\left(\frac{x' + \frac{\pi r}{2}}{2r}\right) =$$

$$-\frac{2r^2}{h} l_e \tan\left(\frac{x'}{2r} + \frac{\pi}{4}\right);$$

or dropping primes and reducing

$$(40)\quad y = -\frac{2r^2}{h} l_e \left(\frac{1 + \tan\frac{x}{2r}}{1 - \tan\frac{x}{2r}}\right)$$

In (40) if

$$x = o, y = -\frac{2r^2}{h} l_e(1) = o;$$

$$x = \frac{\pi r}{2}, y = -\frac{2r^2}{h} l_e(\infty) = -\infty;$$

$$x = -\frac{\pi r}{2}, y = -\frac{2r^2}{h} l_e(o) = +\infty.$$

$\therefore$ the curve is asymptotic to the right lines

$x = \pm \frac{\pi r}{2}$; *i. e.*, to l X and D D'.

If the obliquity of the arch in fig. (2) were in the *opposite direction*, the right hand members of equations (1), (38), (39), and (40) would all be *positive*.

To adapt equation (39) to convenient computation, let $x = n \pi r$, which is equivalent to dividing the distance $\pi r =$ O, X into n equal parts, for which ordinates are to be calculated.

$\therefore$ Substituting common logarithms for Naperian,

$$(41)\ y = -\frac{2r^2}{h} \cdot \frac{1}{M} l_a \tan \frac{n\pi}{2},$$

in which l_e signifies common logarithm and M is the modulus of the common system. From this equation any number of ordinates may be easily calculated for the construction of the curve $k\ O_2\ m$.

The equation of the curve K O P P_1 will next be found. This is the horizontal projection of the curve on the soffit of which $k\ O_2\ m$ is the development. Its vertical projection is of course the semicircle D′ V C_2. It is plain that for any value of y the x for the new equation will bear a certain relation to the x of equation (39), and hence may be derived from it. Call the co-ordinates of K O P x' and y', x and y being those of equation (39),

$\therefore\ x' = -r\left(1 - \cos\frac{x}{r}\right)$; whence $x = r\cos^{-1}\left(\frac{x'+r}{r}\right)$, and $y' = y$, the origin being at O_1.

Substituting in equation (39) and omitting primes,

$$(42)\ y = -\frac{2r^2}{h}\ l_e \tan\tfrac{1}{2}\left[\cos^{-1}\left(\frac{x+r}{r}\right)\right]$$

In (42) change the origin to O, and we have

$$(43)\quad y = -\frac{2r^2}{h} l_e \tan \tfrac{1}{2}\left(\cos^{-1}\frac{x}{r}\right).$$

Now we have by trigonometry

$$\cos^{-1}\frac{x}{r} = \tan^{-1}\frac{\sqrt{1-\frac{x^2}{r^2}}}{\frac{x}{r}} = \tan^{-1}\frac{\sqrt{r^2-x^2}}{x}$$

also

$$\tan \tfrac{1}{2}\left(\left(\tan^{-1}\frac{\sqrt{r^2-x^2}}{x}\right)\right) = \frac{-1+\sqrt{1+\frac{r^2-x^2}{x^2}}}{\frac{\sqrt{r^2-x^2}}{x}}$$

$$= \frac{r-x}{\sqrt{r^2-x^2}} = \sqrt{\frac{r-x}{r+x}}$$

Substituting in (43) we have

$$(44)\ y = \frac{-2r^2}{h} l_e \sqrt{\frac{r-x}{r+x}} = \frac{r^2}{h} l_e \left(\frac{r+x}{r-x}\right),$$

which is the equation of K O P with the origin at O, O Q being the axis of y.

In (44) if $x = o$, $y = \frac{r^2}{h} l_e (1) = o$

" $x = r$, $y = \frac{r^2}{h} l_e (\infty) = \infty$

" $x = -r$, $y = \frac{r^2}{h} l_e (o) = -\infty$.

Equation (39) solved for x is:

(45) $x = 2\, r\, tan^{-1}\, e^{-\frac{h\, y}{2\, r^2}}$

in which e is the base of the Naperian system of logarithms. It is sometimes desirable to consider y as the independent variable, in which case the equation takes this form.

We will now give a table of values of $\frac{1}{M} l_a\, tan\, \frac{n\, \pi}{2}$ corresponding to a series of values of n, also the values of x in equation (44) for which the ordinates are equal to the corresponding ordinates of the curve $k\, O_a\, m$.

TABLE III.

Values of n in Equation (41)	Values of $\frac{1}{M} l_a \tan \frac{n\pi}{2}$	Values of x in Equation (44) for which y is equal to the y of Equation (41).	REMARKS.
0.01	— 4.2331	0.99951r	*N.B.*—The values of x in column 3 are to be laid off from the *axis* of the *cylinder* as the axis of y. *In equation* (41) *the axis of* y *is* $O_1 D_2$. To obtain the corresponding values of x for the curve I O L M, *substitute* r_1 *for* r in the 3d column, the axis of y being the same.
0.02	— 3.4601	0.99803r	
0.03	— 3.0541	0.99556r	
0.04	— 2.7659	0.99211r	
0.05	— 2.5421	0.98769r	
0.10	— 1.8427	0.95106r	
0.15	— 1.4266	0.89101r	
0.20	— 1.1240	0.80902r	
0.25	— 0.8810	0.70711r	
0.30	— 0.6742	0.58779r	
0.35	— 0.4897	0.45399r	
0.40	— 0.3195	0.30902r	
0.45	— 0.1577	0.15643r	
0.50	— 0.0000	0.00000r	

By means of this table the curves $k\,O_2\,m$ and K O P may be easily and accurately constructed, as well as the curves I O L M and N R O_4 for the Ex s.

For the curve I O L M, which is the

intersection of a c j s, with a cylinder concentric with the soffit, we have if x be the abscissa of K O P, x' the abscissa of I O L M and r_1 the radius of the concentric cylinder,

$$\frac{x}{x'} = \frac{r}{r_1} \text{ or } x = \frac{rx'}{r_1}.$$

This value in equation (44) gives

$$(46)\ y = \frac{r^2}{h} l_e \left(\frac{r_1 + x}{r_1 - x}\right) \text{ (primes omitted).}$$

For the curve N R O_4 which is the development of I O L M, calling the abscissa of k O_2 m x, and that of N R O_4 x', we have

$$\frac{x}{x'} = \frac{r}{r_1};\ \therefore x = \frac{rx'}{r_1},$$

which, in equation (40), gives, omitting primes,

$$(47)\ y = -\frac{2r^2}{h} l_e \left(\frac{1 + tan\ \frac{x}{2r_1}}{1 - tan\ \frac{x}{2r_1}}\right)$$

which is the equation of N R O_4 with the origin at O_4. The ordinates for this

curve are the same as those for the curve $k\ O_2\ m$ when we give the proper values to x, that is, make $x = n\ \pi\ r_1$, and measure it from the line $B_1\ B_3$ as the axis of ordinates.

The curve S V′ T is a projection of the curve K O P P_1 on a plane parallel to the P F, of which $p\ q$ is the horizontal trace. In constructing an arch by this method it would be desirable to project it on such a plane, and hence this curve would be needed. It cuts at right angles the projection on its plane of any ellipse cut from the soffit by a plane parallel to the P F, and its equation is found by a process similar to that by which equation (39) was obtained. Let $g\ p$ be the axis of x and O′ V′ the axis of y. The equation of the ellipses to which the curve is to be normal at point of cutting is

$$(48)\quad b^2\ (x - a_1)^2 + a^2\ y^2 = a^2\ b^2$$

in which a_1 is the variable abscissa of the centre. Differentiating

$$\frac{dy}{dx} = -\frac{b^2\ (x - a_1)}{a^2\ y}$$ or substituting value of a_1 from (48).

$$\frac{dy}{dx} = \frac{b\sqrt{b^2 - y^2}}{a\,y}.$$

This in the formula $1 + \frac{dy}{dx}\cdot\frac{dy'}{dx'} = o$,

gives $\frac{dy'}{dx'} = -\frac{a\,y}{b\sqrt{b^2 - y^2}}$; or, dropping primes, since x and y in the two members refer to the same point,

$$dx = -\frac{b}{a}\,y^{-1}\,dy\,\sqrt{b^2 - y^2}$$

Whence, by integration

$$x = \frac{b}{a}\left\{ b\,l_e\sqrt{\frac{b + \sqrt{b^2 - y^2}}{b - \sqrt{b^2 - y^2}}} - \sqrt{b^2 - y^2} \right\} + c$$

If we let $x = o$ where $y = b$—*i. e.*, place the centre of the curve at O′—then $c = o$, and

(49)

$$x = \frac{b}{a}\left\{ b\,l_e\sqrt{\frac{b + \sqrt{b^2 - y^2}}{b - \sqrt{b^2 - y^2}}} - \sqrt{b^2 - y^2} \right\}$$

This curve is symmetrical about both axes of reference, and is asymptotic to the axis of x.

To obtain (49) in a convenient form for computation, place $y = n\,b$, then

$$(50)\ x = \frac{b^2}{a}\left\{ l_e \sqrt{\frac{1+\sqrt{1-n^2}}{1-\sqrt{1-n^2}}} - \sqrt{1-n^2} \right\}$$

From this equation have been calculated the values of the parenthesis for a series of values of n, as given in the following table.

TABLE IV.

Values of n	Values of $\frac{a\,x}{b^2}$.
0.1	± 2.000
0.2	± 1.313
0.3	± 0.921
0.4	± 0.650
0.5	± 0.450
0.6	± 0.299
0.7	± 0.184
0.8	± 0.093
0.9	± 0.032
1.0	0.000

The c j c's on the development of the soffit may be constructed by means of a pattern, one side of which is cut by the curve k O_2 m, and the other side is straight and parallel to l X. By placing this pattern upon the curve k O_2 m, laying a straight-edge along the back, and then sliding the pattern till it passes through the different points of division on the line n o, the proper portion of the pattern for each curve will be found. For construction upon a very large scale —as, for instance, upon a platform the true size of the arch—this method would be impracticable. The point of the curve k O_2 m which passes through any point of division on the curve n o may then be found by calculation. Find by measurement or computation the value of x for the point of division—*i. e.*, its distance from the line D D_2; take this distance as a fractional part of π r—*i. e.*, as a value of n—and, substituting in equation (41), find the corresponding value of y; this will be the constant c of equation (38). Subtracting this from the ordinates

found from Table III. will give the ordinates of the curve measured from a line parallel to O_1 X through the point of division. It would also be desirable to determine the exact point in which any c j c cut the curve D_2 C_2. We can approximate very closely to this as follows: Find the point as nearly as possible by sketching in the curve from Table III.; through the point thus found draw a parallel to O_1 X; find the distance from this parallel to the one drawn through the point of division on *n o* corresponding to the same c j c; add this distance to the value of *c* found as above; take this as the value of *y* in equation (45), and compute from it the corresponding value of *x;* this will be the true abscissa of the curve on the line parallel to O_1 X through the point as first found, and of course will give the intersection of the c j c with the curve D_2 C_2 with great accuracy.

The h j s's are, of course, planes parallel to the P F. The c j s's are a species of conoid generated by a right line moving on the axis of the

cylinder as one directrix, a c j c as another, and remaining always perpendicular to the former. Any plane perpendicular to the axis is therefore a plane director. The intersection of any c j s with the P F will be a curve, several points of which will be needed in a construction upon a large scale. These may easily be found by drawing one or more semicircles between $D'V'C_2$ and $B'V'A_2$, finding, by Table III., the curves corresponding to I O L M, for the cylinders of which these semicircles are the vertical projections, and then erecting perpendiculars to the ground line from the points of intersection of these curves with the P F (or planes parallel to it) to meet the semicircles. Projected on a plane parallel to the P F, these curves of intersection of the c j s's with the P F will be normal to the elliptical section cut from the soffit by the P F at the points in which they cut it, and hence will be tangent to the projections on the same plane of the c j c's. All the above remarks apply also to the intersection of

a c j s with any h j s—*i. e.*, any plane parallel to the P F.

In order to cut the voussoirs patterns must be made of the cylindrical and plane faces of each. It will also facilitate the operation to construct each in isometric projection, drawing on the cylindrical face one or more elements of the cylinder as guides in the cutting. Cut first the two plane faces of the voussoir precisely parallel to each other; cut roughly another plane face, making an angle with these two approximately equal to that between the P F and a tangent plane to the soffit at some point of the cylindrical face of the voussoir (*i. e.*, to the angle β of equation (51), from which equation its value may be found); lay the stone in such a position that the first two faces shall be vertical, and the third uppermost; apply to the vertical faces the patterns for the ends of the voussoir, with the edges next the soffit uppermost, their relative position being fixed by measurement from the drawings; mark out the ends by the patterns, and also the points where one or more elements of

the cylinder pierces the h j s; sink drafts in the upper face connecting these points, and then cut the cylindrical face by a templet cut to the radius of the soffit, and applied at right angles to the elements. Next apply the pattern of the soffit, and draw by it the lines *a b*, *c d*, for the edges of the stone. In the figure *a d* is an element of the cylinder, the stone being seen from above, and being taken from a course near the crown of the arch.



The warped faces can be cut by means of a templet of the form shown in the accompanying figure. The arc *a b c*)) *a' b' c'* is cut to the radius of the cylinder, and the arm *a d*)) *a' d'* is firmly fixed so as to be normal to the arc at the point



a)) a'. The cross-bar $e\,f$ is perpendicular to $a\,c$, and its upper edge also perpendicular to the plane of $a\,b\,c$)) $a'\,b'\,c'$ and $a\,d$)) $a'\,d'$. g)) g' and g_1)) g' are braces. Suppose the stone were cut, then, if the curved edge of the templet were applied to the cylindrical face with the edge of cross-bar $e\,f$ coinciding with an element of the cylinder, and the point a)) a' at the edge of the voussoir, the edge $a\,d$)) $a'\,d'$ of the normal arm would lie upon the warped face, and coincide with an element of it. If a number of drafts be sunk in the stone, then, by means of this templet, the warped faces can be easily cut. It only remains to cut the Ex s of the voussoir. If this surface is to be a cylinder concentric with the soffit, the intersections of this cylinder with the c j s's can be at



once laid off on the stone by the aid of the templet. Measure on $a\,d$)) $a'\,d'$ from a')) a' the distance $r_1 - r$, between soffit and Ex s; mark the point, and, applying the templet as described above, mark on the stone any number of points in the required curve. If the arch is to be built upon with stone, it would be better to cut the Ex s in steps, each stone having one or more horizontal and vertical plane faces when in position in the arch. This would not add to the difficulty of *cutting* the stones, though it would somewhat to that of making the drawings. This way of cutting the stones is shown in the drawing of the arch according to the "cow's horn" method.

The diedral angle at the edge of a voussoir must not be less than a certain limit, otherwise the stone will be deficient in strength at this edge. The limit is usually taken at 60°; hence it follows that a *full centred* arch should not be constructed by this method with a greater obliquity than 60°; but, as the

angle between a tangent plane to the soffit and the P F *increases* as the element of contact is taken higher above the springing plane, up to 90° at the crown, it is evident that a *segmental* arch may be built with a greater obliquity than 60°, whose diedral angles will be within the limits. To find the chord of the segment (*i. e.*, the span),

Let α = C, D, D′ = obliquity of arch.

Let β = angle between P F and tangent plane to soffit; *i. e.*, its limiting angle.

Let γ = angle between the tangent plane to soffit and the H P.

Then we have a right-angled spherical triangle, and by spherical trigonometry,

$$\cos \beta = \cos \alpha \sin \gamma$$

$$\text{or } \sin \gamma = \frac{\cos \beta}{\cos \alpha},$$

$$(51) \quad \therefore \text{Span} = 2 r \sin \gamma = \frac{2 r \cos \beta}{\cos \alpha}$$

If we let $\beta = 60°$, then $\cos \beta = \frac{1}{2}$;

$$\therefore \text{Span} = \frac{r}{\cos \alpha} = r \text{ secant } \alpha.$$

Also $\cos \alpha = \frac{r}{\text{span}}$ from which we can determine the limit of obliquity for a given segment.

If the span $= r$, then $\cos \alpha = 1$, and $\alpha = o$. Therefore we may give any obliquity to the arch that we please without passing the limit. If $\alpha = 30°$, the limiting span is

$$\text{Span} = \frac{2\,r}{\sqrt{3}} = 1.1546\,r.$$

The security of the arch constructed after this method will next be considered. In Fig. 2 the curves Q Γ' a and Q P_1' b are the vertical projections of the curves cut from the c j s, whose directrices are the axis of the arch, O Q, and the curve K O P_1 by the planes P c and P_1 O_1. These curves will be shown to have maximum points at P P′ and P_1 P_1' where they pierce the soffit. h K O L g is the horizontal projection of the curve cut from

the same c j s by the horizontal plane $e f$, and it will be shown that its tangent at the point of piercing the soffit is perpendicular to the P F. It will likewise be shown that the tangent plane to the c j s at any point of the c j c is perpendicular to the tangent to the elliptical section parallel to the P F at that point. Hence, where it intersects the soffit every c j s is exactly normal to that direction which we have assumed to be the direction of the pressure.

First to obtain the equation of a c j s. Let the line O X be the axis of x, the line Z O Q the axis of z; then let the axis of y be a vertical line through O. Then the equations of the curve K O P P_1 will be

$$(a) \qquad x^2 + y^2 = r^2$$

$$(b) \qquad z = \frac{r^2}{h} l_e \left(\frac{r - x}{r + x}\right).$$

Equation (b) is derived from equation (44) by substituting z for y and changing the sign of the right hand member, because the axis O Q in equation (44) was considered as positive from O toward Q,

while now it is taken as positive from O toward Z.

Let $\frac{h}{r^2} = c$, and solve equation (*b*) for x.

$$\therefore\ e^{cx} = \frac{r - x}{r + x};\ \text{whence}$$

$$(52) \qquad x = r.\ \frac{1 - e^{cx}}{1 + e^{cx}}.$$

For the point x_1 we have

$$(53) \qquad x_1 = r\ .\ \frac{1 - e^{cx_1}}{1 + e^{cx_1}}$$

Substitute value of x_1 from (53) in (*a*).

$$\therefore y_1^2 = r^2 - r^2\ .\ \frac{1 - 2\,e^{cx_1} + e^{2cx_1}}{1 + 2\,e^{cx_1} + e^{2cx_1}}$$

$$= r^2\left(\frac{1 + 2\,e^{cx_1} + e^{2cx_1} - 1 + 2\,e^{cx_1} - e^{2cx_1}}{(1 + e^{cx_1})^2}\right)$$

$$(54) \qquad \therefore\ y_1 = \frac{2\,r\,\sqrt{e^{cx_1}}}{1 + e^{cx_1}}$$

The equation of a line in X Y through the points $(x_1\ y_1)$ and $(x_2\ y_2)$ is

$$(55) \qquad \frac{y - y_2}{x - x_2} = \frac{y_1 - y_2}{x_1 - x_2}.$$

Since O Q is a directrix of the surface, we shall have

(56) $\qquad x_2 = y_2 = o$

$\therefore$ substituting from (53), (54), and (56) in (55)

$$\frac{y}{x} = \frac{2\,r\,\sqrt{e^{cz}{}_1}}{1 + e^{cz}{}_1} \cdot \frac{1 + e^{cz}{}_1}{r\,(1 - e^{cz}{}_1)};$$

or reducing and making z_1 general by dropping the subscript,

$$(57) \qquad \frac{y}{x} = \frac{2\,e^{\frac{cz}{2}}}{1 - e^{cz}} = \frac{2\,e^{\frac{hz}{2r2}}}{1 - e^{\frac{hz}{r2}}},$$

which is the equation of a c j s.

Intersect this surface by the vertical plane P c d, whose equation is

$$(58) \qquad z = \frac{2\,r}{h}\,(a_1 - x),$$

in which a = O c = intercept on X, and $\frac{2\,r}{h} = tan\ \alpha$.

Substituting value of z from (58) in (57),

$$(59) \qquad \frac{y}{x} = \frac{2\,e^{\frac{a_1 - x}{r}}}{1 - e^{\frac{2\,(a_1 - x)}{r}}} = \frac{2\,e^{u}}{1 - e^{2u}}$$

if we let $u = \frac{a_1 - x}{r}$.

This is the equation of the curves Q P′ a, Q P_1′ b, etc. In (59) if $x = a_1$, $y = \infty$; $\therefore$ the line $x = a_1$ is an asymptote. Also if $x = o$, $y = o$, and if $x = \pm \infty$, $y = o$, and the axis of x is an asymptote.

Differentiating (59)

$$\frac{dy}{dx} = \frac{2(1-e^{2u})\left(e^u + x\,e^u\left(\frac{du}{dx}\right)\right) + 4\,e^{3u}\,x\left(\frac{du}{dx}\right)}{(1 - e^{2u})^2}$$

But $\frac{du}{dx} = -\frac{1}{r}$, therefore after reduction

$$(60)\quad \frac{dy}{dx} = 2\,e^u\left\{\frac{r - x - (r+x)\,e^{2u}}{r\,(1-e^{2u})^2}\right\}$$

For a maximum $\frac{dy}{dx} = o$;

$$\therefore\quad r - x - (r+x)\,e^{2u} = o.$$

$$(61)\qquad e^{2u} \frac{r-x}{r+x};$$

This equation gives the values of x for which y is a maximum.

Now eliminate y between equations (59) and (a),

$$\therefore x^2 + \frac{4\, e^{2u}\, x^2}{(1 - e^{2u})^2} = r^2\text{; whence}$$

$$x^2 \left(\frac{1 + e^{2u}}{1 - e^{2u}}\right)^2 = r^2\text{; therefore solving for } e^{2u}.$$

$$(61') \qquad e^{2u} = \frac{r - x}{r + x}.$$

This equation, which gives the x co-ordinate of the point of intersection of the curves Q P′ a, Q P′ b, etc., with the circle D′ V C_2, is identical with (61), which gives x where y is a maximum; therefore the curve whose equations are

$$\begin{cases} y = \dfrac{2\, e^u x}{1 - e^{2u}} \\ z = \dfrac{2\, r}{h}(a_1 - x) \end{cases}$$

has its tangent line horizontal at the point of piercing the soffit.

To find the inclination of the tangent at the point where the curve pierces a cylinder concentric with the soffit whose radius is r_1. If the co-ordinates of this point be x_1 y_1 we have by substituting in (61′), u_1 for u, r_1 for r, and x_1 for x,

$$e^{2u_1} = \frac{r_1 - x_1}{r_1 + x_1}; \quad \therefore \; e^{u_1} = \sqrt{\frac{r_1 - x_1}{r_1 + x_1}}$$

Substituting these values in (60),

$$\frac{dy_1}{dx_1} = \frac{2}{r}\sqrt{\frac{r_1 - x_1}{r_1 + x_1}}\left\{\frac{r - x_1 - (r + x_1)\dfrac{r_1 - x_1}{r_1 + x_1}}{\left(1 - \dfrac{r_1 - x_1}{r_1 + x_1}\right)^2}\right\}$$

whence by reduction,

$$(62) \quad \frac{dy_1}{dx_1} = \frac{(r - r_1)\sqrt{r_1^2 - x_1^2}}{r\,x_1} = -\frac{\delta y_1}{r\,x_1},$$

if we let $r_1 - r = \delta$.

If we multiply $\frac{dy_1}{dx_1}$ by $\cos\alpha$, we obtain the tangent of the angle between the tangent line to the curves c P ,, Q P′ a, O_1 P_1 ,, Q P_1' b, etc., at the point of piero-

ing the Ex s and the H P. Call this angle t, then

$$(63) \qquad \tan t = -\frac{\delta\, y_1 \cos\alpha}{r\, x_1}.$$

Suppose $\alpha = 60°$, $\frac{\delta}{r} = \frac{2}{15}$, then

If $x_1 = r_1 \cos 10°$, $y_1 = r_1 \sin 10°$, and $t = 0°\ 40'\ 20''$
" $x_1 = r_1 \cos 20°$, $y_1 = r_1 \sin 20°$, and $t = 1°\ 23'\ 20''$
" $x_1 = r_1 \cos 30°$, $y_1 = r_1 \sin 30°$, and $t = 2°\ 12'\ 15''$

Intersect the locus of equation (57) by the plane

$$y = b;$$

$$\therefore \quad \frac{b}{x} = \frac{2\, e^{\frac{cz}{2}}}{1 - e^{cz}};$$

$$\therefore\ b\, e^{cz} + 2\, x\, e^{\frac{cz}{2}} - b = o;$$

solving this for $e^{\frac{cz}{2}}$ as a quadratic,

$$e^{\frac{cz}{2}} = \frac{-x \pm \sqrt{x^2 + b^2}}{b}$$

$$(64) \quad \therefore z = \frac{2}{c}\, l_e \left(\frac{-x \pm \sqrt{x^2 + b^2}}{b}\right).$$

Differentiating and reducing,

$$(65)\ \frac{dz}{dx} = \frac{2}{\mp c\sqrt{x^2 + b^2}} = \frac{2r^2}{\mp h\sqrt{x^2 + b^2}}$$

When $z = o$, $\frac{dz_o}{dz_o} = \mp \frac{2r^2}{bh} = \mp \frac{r}{b} tan\ \alpha.$

" $b = r_1$ and $x = o$, $\frac{dz_{or_1}}{dx_{or_1}} = \frac{2r}{h}.\frac{r}{r_1} = \frac{r}{r_1} tan\ \alpha$

To find the angle at which the locus of (64) pierces a cylinder concentric with the soffit, eliminate y between $y = b$ and $x^2 + y^2 = r_1^2$.

$$\therefore\ x_1^2 = r_1^2 - b^2.$$

Substitute this value of x in (65),

(66)

$$\therefore \frac{dz_1}{dx} = \frac{2r^2}{\mp h\sqrt{r_1^2 - b^2 + b^2}} = \mp \frac{2r}{h}.\frac{r}{r_1} = \frac{r}{r_1} tan\ \alpha.$$

If $r_1 = r$, $\frac{dz_2}{dx_1} = tan\ \alpha$. We see therefore that the locus of (64) pierces the soffit at the angle α.—*i. e.*, its tangent is there perpendicular to the P F—and that it pierces any cylinder concentric with

the soffit at a constant angle for any given value of α, no matter what value b may have.

The surface is thus seen to differ very essentially from the helicoid previously considered, as regards tendency to sliding on the coursing joints, as is indeed evident from a comparison of the two drawings.

The tangent plane to the c j s at any point of the c j c, as P P′, must contain the element of the surface through the point and the tangent line at the point to the curve cut out by a horizontal plane through the point; therefore it must be perpendicular to the P F. The tang. of the angle between it and the H P will be equal to

(67) tan 'P Q C_2 $cosec\ \alpha = tan$ N

if N be the angle between the normal at P P′ and a vertical line; but this is also the expression for the tangent of the angle between a vertical line and the tangent line at P P′ to the elliptical section of the soffit parallel to the P F; therefore the assumed direction of pressure is normal

to the c j s at any point of the c j c. This result might have been predicted from the mode of construction of the c j c's.

The curve cut fr om a c j s by the plane

$$(68) \qquad s = \frac{h}{2r}(x - a_1)$$

parallel to the P F is always convex towards the springing plane between the soffit and Ex s. Its equation found by substitution in (57) is

$$(69) \quad \frac{y}{x} = \frac{2e^{\frac{h^2}{4r^2}(x-a^1)}}{1-e^{\frac{h^2}{2r^2}(x-a^1)}} = \frac{2e^v}{1-e^{2v}}$$

if we place $\frac{h^2}{4r^2}(x - a_1) = v.$

By differentiation and reduction we obtain in the same way in which we found (62)

$$(70) \quad \frac{dy_1}{dx_1} = \frac{y_1}{x_1}\left(\frac{4r^2 + h^2 r_1}{4r^2}\right),$$

which is the tangent of the angle between the tangent line to the locus of (69) at point of piercing the cylinder whose ra-

dius is r_1 and the horizontal plane. To obtain the angle between the tangent line to the curve in space whose equations are (68) and (69) and the H P, multiply (70) by $\sin \alpha = \frac{2r}{\sqrt{h^2 + 4r^2}}$

Call this angle t_1, then

$$(71) \quad tan\, t_1 = \frac{y_1}{x_1}\left(\frac{4r^2 + h^2}{2r\sqrt{h^2 + 4r^2}}\, r_1\right) = \frac{y_1}{x_1} \cdot \frac{r \sin^2 a + r_1 \cos^2 \alpha}{r \sin \alpha}$$

If $r_1 = r$, which gives the point of piercing the soffit,

$$(72) \quad tan\, t_s = \frac{y_1}{x_1} \cdot \frac{\sqrt{4r^2 + h^2}}{2r} = \frac{y_1}{x_1} cosec\, \alpha,$$

which is identical with equation (67).

If $\frac{r_1}{r} = \frac{17}{15}$, and $\alpha = 60°$, then

when $\frac{y_1}{x_1} = tan\, 10°$, $t_1 = 11° 52' 50''$, $t_s = 11° 30' 30''$

" $\frac{y_1}{x_1} = tan\, 20°$, $t_1 = 23° 28' 16''$, $t_s = 22° 47' 45''$

" $\frac{y_1}{x_1} = tan\, 30°$, $t_1 = 34° 33' 30''$, $t_s = 33° 41' 24''$

The points for which t_1 and t_s are found being on the same radius are of course on different curves, though these curves are so near together that the difference between the angles t_1 and t_s is very nearly the same as the difference between the slope of the tangents to a single curve at the points of piercing the soffit and Ex s.

The function $n = t_1 - t_s$ is found by differentiation to be a maximum when

$$\frac{y_1}{x_1} = \frac{1}{\sqrt{\sin^2 \alpha + \frac{r_1}{r} \cos^2}} = \tan 44^\circ 32'$$

where α and $\frac{r_1}{r}$ have the values assigned above. The maximum value of the function in this case is $t_1 - t_s = 55' 31''$.

It appears, therefore, that at *no* point on the c j s, between the soffit and the Ex s does the normal to the c j s vary to any extent from the assumed direction of pressure.

COW'S HORN METHOD.

IN this method the soffit is a warped surface called the *Corne de Vache*, or Cow's Horn, generated in the following

manner. A right line moves on three directrices, which are: 1st, two equal ellipses in parallel, vertical planes, having their transverse axes in the springing plane of the arch; and 2d, a right line drawn in the springing plane perpendicular to the plane of the ellipses, through the centre of the parallelogram formed by joining the extremities of the transverse axes of the ellipses. These ellipses may, of course, as a particular case, be circles. In Fig. 3, the plane of one face of the arch is taken as the V P, and the springing plane is the H P. In referring to Fig. 3, the following notation will be employed. Any letter with *h* written above it as an exponent, means the *horizontal* projection of a point, and the same letter, with exponent *v*, is the *vertical* projection of the same point: and this point will be referred to as the point A, B, etc.. *i. e.*, the point whose projections are A^h A^v, B^h B^v, etc. A line drawn through these two points would be, therefore, the line A B. If one projection of a point is in the ground line, *h* or

v, as the case may be, is replaced by *o*, and if the point itself is in the ground line, it will be designated by the letter alone without exponent.

In Fig. 3, the parallelogram A^h B^h C D is the horizontal projection of the soffit. Its centre O is the point through which the rectilinear directrix of the soffit is drawn perpendicular to the V P, since this coincides with a P F. The three directrices of the cow's horn surface are then the ellipses D S I C, and A K N B, and the right line O Z lying in the H P. The elements of the surface are to be drawn so as to cut these three directrices. The vertical projection of O Z is a point in the ground line at O^v, hence the vertical projections of the elements will be lines radiating from this point. By dropping perpendiculars from the points where the vertical projections of the elements meet the vertical projections of the elliptical directrices to the horizontal projections of the same, the horizontal projections of the elements will be found, as will be seen in the case of the elements

R S, P Q, etc. *The elements of the surface are the edges of the voussoirs*—that is, the c j c's, which, therefore, in this method become right lines, while the h j c's, being sections of the soffit parallel to the P F, are curves of the 4th degree. It is, of course, impossible to *develop* the soffit, since the consecutive elements are not in the same plane.

The arch must be divided up into courses on the *median section* in order that the two faces may be alike. To find this, draw the vertical projections of a number of elements, and bisect the portion of each included between the points in which it cuts the vertical projections of the elliptical directrices; through these points of bisection the median curve may be drawn. In Fig. 3, it is the line L T, and is only drawn as far as the crown of the arch. The length of this median curve would have to be ascertained by construction upon a large scale, and accurate measurement. It may then be divided into a convenient odd number of equal parts, and the elements of

the surface, which are the c j c's drawn through the points of division.

The h j s's in this method, are planes parallel to the planes of the faces of the arch, while the c j s's are hyperbolic paraboloids the method of whose construction will next be shown. It will first be shown that a hyperbolic paraboloid may be drawn having an element in common with any warped surface, and normal to this surface at every point of the common element. It is proved in works on descriptive geometry, that, if two warped surfaces have a common element, and have common tangent planes at three different points of this element, they are tangent to each other throughout the length of this element. Therefore, we can always draw a hyperbolic paraboloid *tangent* to a warped surface along an element; for draw tangent planes at three points of any element, and in these planes, through the points of tangency, draw right lines parallel to some given plane; if a rectilinear generatrix be moved on these lines, a hyperbolic para-

boloid will be generated tangent to the warped surface along the element. Now, revolve this tangent surface about the common element as an axis through an angle of 90°; it will then be normal to the other surface at every point of the element. If the lines drawn in the tangent planes are *perpendicular* to the common element, after revolution through 90°, they will be perpendicular to the tangent planes, and hence normals to the warped surface. Hence it follows that the directrices for a c j s may be three normals to the soffit, drawn at any convenient points of the corresponding c j c, or element. The points at which normals are most easily constructed are those in which the element cuts the three directrices, but as the intersection with the rectilinear directrix will generally be beyond the limits of the drawing, some other point must be used instead of this one. A method will now be given by which a tangent line can be easily and simply constructed at any point of any section of the cow's horn surface, by a

plane parallel to the elliptical directrices. This tangent line being found, of course the normal to the surface at the point of



tangency can be drawn at once. Let A V B and C V D be vertical projections

of the elliptical directrices, P_3 that of the rectilinear directrix, P_3 X that of the element through P_1, which is a point of some section of the soffit by a plane parallel to the P F, and O F and E F tangents to the curves A V B and C V D, at the points where they are cut by P_3 X. E F and O F will meet on P_3 F because this is the axis radical of the two curves.

Let O E $= a$, O F $= b$, P_3 O $= a_1$ and O $P_4 = b_1$. Take O as the origin of co-ordinates, the line P_3 X as the axis of abscissas, and the line O Y as the axis of ordinates. Then the equation of the tangent line E F will be

$$\frac{x}{a} + \frac{y}{b} = 1; \tag{72}$$

that of the line P_3 P_5,

$$\frac{x}{-a_1} + \frac{y}{b_1} = 1; \tag{73}$$

and that of the tangent line O F,

$$x = 0. \tag{74}$$

We will now find the equation of the line cutting O X and P_3 P_5 in such a manner that $\frac{O\ P_1}{P_1\ E} = \frac{P_4\ P_2}{P_2\ P_5}$. Let O P_1=

$n \times OE = n\,a$. To find the co-ordinates of the point P_5 eliminate between (72) and (73)

$$\therefore\ y_5 = b - \frac{b}{a}\,x_5 = b_1 + \frac{b_1}{a_1}\,x_5$$

$$x_5 = \frac{a\ a_1\ (b - b_1)}{a_1\ b\ +\ a\ b_1},\ \text{similarly}$$

$$y_5 = \frac{b\ b_1\ (a\ +\ a_1)}{a_1\ b\ +\ a\ b_1}.$$

For the point P_4 the co-ordinates are

$$x_4 = 0, \qquad y_4 = b_1$$

Hence for P_2 we shall have

$$x_2 = n\,x_5 = \frac{n\ a\ a_1\ (b - b_1)}{a_1\ b\ +\ a\ b_1}$$

$$y_2 = b_1 + n(y_5 - b_1) = \frac{b_1\ (a_1\ b + a\,b_1 - na\,(b_1 - b))}{a_1\ b\ +\ a\ b_1}\ ;$$

and for P_1, $x_1 = n\,a$, $y_1 = 0$.

Substituting these values of $x_1\ y_1$, $x_2\ y_2$ in the equation of a line through two points

$$(y - y_1)\ (x_1 - x_2 = (x - x_1)\ (y_1 - y_2)$$

we have after reduction,

$$(75)\quad y = \frac{(na - x)\ (a_1\ b + a\,b_1 - na\,(b_1 - b))}{n\ a\ (a\ +\ a_1)}$$

which is the required line.

Now in this equation we may give to b_1 any value we please, positive or negative; suppose it to change gradually in value from some positive quantity to some negative, the line G P_1 will change position accordingly, and at the instant in which b_1 passes through zero it will be tangent to the section through P_1; for the law of this curve of section is, that it cuts off an nth part of the portion of any radial line included between the two curves A V B and C V D; hence at the instant that $b_1 = 0$ the line G P_1 coincide with an element of the curve. In the figure G P_1 is this limiting case; *i. e.*, the tangent at P_1, and the line of equation (75) would cut the axis of y very slightly nearer to F, but the two lines would so nearly coincide for this position of P_3 P_5, that G P_1 is made to answer for both. Now in equation (75) make $b_1 = 0$ and we have the equation of the tang. to the curve of section.

$$(76) \quad \therefore y = \frac{b\,(n\,a - x)}{n\,a} \frac{(a_1 + n\,a)}{(a + a_1)}$$

For the intercept on Y let $x = 0$.

$$(77) \quad \therefore y_0 = \frac{b\,(a_1 + n\,a)}{a + a_1}$$

or putting it into the form of a proportion,

(78) $a + a_1 : n\,a + a_1 :: b : y_0$.

Hence to draw a tangent at any point of a curve of section of a cow's horn surface by a plane parallel to the curve directrices, draw the vertical protection of the element through the point (V P supposed parallel to P F), and tangents to the curved directrices at their points of intersection, with the element; lay off E H and P_1 I each equal to P_2 O $= a_1$; draw H F to the point of intersection of the tangents previously drawn, and I G parallel to H F; through G draw G P_1, then will G P_1 be the required tangent line; for

$$O\,H = O\,E + E\,H = a + a_1,$$
$$O\,I = O\,P_1 + P_1\,I = n\,a + a_1,$$

and O F $= b$; $\therefore$ by (78) O G $= y_0$.

We will now construct a hyperbolic paraboloid normal to the soffit, and intersecting it in the element R S. Since lines perpendicular to each other have

their projections on a plane parallel to one of them perpendicular, the vertical projections of the normals can be drawn at once perpendicular to the tangents to the vertical projections of the curve directrices and the median section at the points R, U, and S. Their horizontal projections will be perpendicular to the horizontal traces of the tangent planes to the soffit at R, U, and S. These tangent planes will of course be the planes through the tangent lines to the soffit at R, U, and S, already drawn, and the element of the surface R S. Portions of their horizontal traces are $\alpha\beta$, $\gamma\delta$, and $\varepsilon\partial$, to which the horizontal projections of the normals S a, U b, and R c are perpendicular. These three normals are the directrices of our c j s. To find an element of the 1st generation, pass a plane through one directrix and find the points where the other two pierce it; join these points by a right line; this line will be an element of the surface. Take, for convenience, the plane which projects a S on the vertical plane of projection,

then b and c will be the points in which the other directrices pierce this plane; therefore $a\ c$ is an element of the first generation. Any number of other elements may now be found by merely dividing up $a\ c$ and S R, or a S and c R proportionally, as in Fig. 3. In the figure the horizontal projections of several elements of each generation are drawn, but the vertical projections of those of the first generation only.

Next the intersections of the c j s with the P F's and with the Ex s must be found. The vertical projection of the intersection of the c j s just constructed with the V P is the line η S^v, of which the portion drawn varies but little from a right line. There are a number of forms in which the Ex s may be cut. It may be a cylinder whose axis passes through O and is parallel to E H; or a co-axial cow's horn surface generated on the extradosal ellipses H I_1 G and E K_1 F; or the exterior surface of each course may be cut like the course M_1 Q_1 by one vertical plane through f and k, and one

inclined through d, f, g and k; or each course may be cut in a series of steps, as in the course P N, by a number of horizontal and vertical planes. The last method would be preferable for the voussoirs at the ends of each course, however the others were cut.

Except in the case where the Ex s is cylindrical, no face of a voussoir can be cut by the aid of a templet. Cut first two plane faces on the stone precisely parallel for the ends of the voussoir. If the Ex s is to be cut in the manner of P N or P_1 N_1, it would be best to cut next the other plane faces of the voussoir of which patterns can be made from the drawings. Then apply the patterns of the heads and mark the lines on the stone, marking also the points where one or more elements of the ruled surfaces forming the soffit and c j s's pierce the plane of the head of the voussoir. The warped faces can then be cut by a straight edge. The soffit face should be cut first, and the elements forming the edges of the voussoir mark-

ed: then all the bounding lines of the coursing joint faces will be given on the stone, and draughts can be sunk by a straight-edge in a direction perpendicular to the soffit edges of the stone by which the c j s's may be cut.

The curves k^0 l m and n o p are the evolutes of the ellipses A K B and D I C, and are convenient in drawing the normals to these curves which are required.

The curved directrices of this arch we take elliptical so as to correspond with the curves cut from the soffit in the other methods by planes parallel to the P F.

In each of the drawings the direct span is 30 ft., the oblique 34.64 ft. $\alpha = 60^0$, and the number of courses is 49.

It is evident from the drawing that if a perpendicular to the H P be erected at the point O, it will pierce the soffit in the line K I, which is parallel to the rectilinear directrix and lower than the highest points of the elliptical directrices, so that the crown of the arch curves

downward toward the middle, from which peculiarity the surface derives its name, "cow's horn." Plainly, if this curvature were so great as to cause the median section of the soffit to be convex toward the springing plane at the crown, the arch would be unsafe; indeed, could not stand at all. We will investigate the conditions under which this will be the case, and to this end will obtain the equation of the surface. Let the line O X be the axis of X, O Z the axis of Z, and let the axis of Y be a vertical line through the origin O. The equations of the three directrices will then be

$$\left.\begin{aligned} &(79)\quad \frac{(x+\varepsilon)^2}{a^2}+\frac{y^2}{b^2}=1 \\ &(80)\quad z=-\delta \end{aligned}\right\}\ \text{Equations of D I C;}$$

$$\left.\begin{aligned} &(81)\quad \frac{(x-\varepsilon)^2}{a^2}+\frac{y^2}{b^2}+1 \\ &(82)\quad z=\delta \end{aligned}\right\}\ \text{Equations of A K B;}$$

(83) $x = 0$, $y = 0$, equation of OZ; in which $\varepsilon = O°q = O°r$, and

$\delta = OK = OI = \frac{1}{2}$ distance between the faces of the arch.

The equation of a plane through the axis of z is

$$y = m x \tag{84}$$

in which m = tangent of angle between plane and H P.

We will now find, by elimination, the co-ordinates of the points in which (79) and (81) pierce this plane, obtain the equations of the element through these points, and then eliminate the constant m. From (79) and (84) we obtain after reduction, and placing $a^2 m^2 + b^2 = k^2$,

$$x_1 = b\left[\frac{-b\varepsilon \pm a\sqrt{k^2 - \varepsilon^2 m^2}}{k^2}\right].$$

Similarly from (81) and (84),

$$x_2 = b\left[\frac{+b\varepsilon \pm a\sqrt{k^2 - \varepsilon^2 m^2}}{k^2}\right].$$

Also from (80) and (82) we have

$$z_1 = -\delta \text{ and } z_2 = +\delta.$$

Substituting these values of x_1 x_2 z_1 and z_2 in the equation $\frac{z - z_1}{x - x_1} = \frac{z_2 - z_1}{x_2 - x_1}$ of a

line through two points in X Z, we have

$$(\varepsilon+\delta)\frac{2b^2\varepsilon}{k^2}=2\delta\left(x-\frac{-b^2\varepsilon\pm ab\sqrt{k^2-\varepsilon^2m^2}}{k^2}\right)$$

and by reduction

$$(85)\qquad b^2\ \varepsilon\ z\ -\ a^2\ \delta\ m^2\ x\ -\ \delta\ b^2\ x$$

$$=a\ b\ \delta\ \sqrt{a^2\ m^2+b^2-\varepsilon^2\ m^2}$$

which is one equation of the element through $(x_1\ z_1)$ and $(x_2\ z_2)$, equation (84) being another.

Squaring (85), introducing the value of m from (84), and reducing, we obtain

$$\delta^2\left(\frac{x^2}{a^2}+\frac{y^2}{b^2}\right)^2-\frac{2\ \delta\ \varepsilon\ x\ z}{a^2}\left(\frac{x^2}{a^2}+\frac{y^2}{b^2}\right)-$$

$$\delta^2\left(\frac{x^2}{a^2}+\frac{y^2}{b^2}\right)+\varepsilon^2\left(\frac{x^2\ z^2}{a^4}+\frac{\delta^2\ y^2}{a^2\ b^2}\right)=0;$$

or factoring,

$$(86)\ \delta\left\{\left(\frac{x^2}{a^2}+\frac{y^2}{b^2}\right)\delta-\frac{2\ \varepsilon\ x\ z}{a^2}-\delta\right\}\left(\frac{x^2}{a^2}+\frac{y^2}{b^2}\right)$$

$$+\varepsilon^2\left(\frac{x^2\ z^2}{a^4}+\frac{\delta^2\ y^2}{a^2\ b^2}\right)=0$$

which is the equation of the cow's horn surface. If ε be taken negative, the ob-

liquity of the arch will be in the opposite direction from that of Fig. 3.

Equation (86) contains only even powers of y, hence the surface is symmetrical with respect to the plane X Z.

If $z = \pm \delta$, it becomes

$$\frac{(x \mp \varepsilon)^2}{a^2} + \frac{y^2}{b^2} = 1,$$

the equations of the curved directrices.

If $x = 0$, we have $y = \pm b\sqrt{1 - \frac{\varepsilon^2}{a^2}}$, two right lines parallel to the rectilinear directrix.

If $y = 0$, then $z = \frac{\delta\,(x \mp a)}{\varepsilon}$.

If z = some constant $= n\,\delta$, we have the intersection by a plane parallel to the P F.

$$(87)\quad \left\{\frac{x^2}{a^2} + \frac{y^2}{b^2} - \frac{2\,\varepsilon\,n\,s}{a^2} - 1\right\}\left(\frac{x^2}{a^2} + \frac{y^2}{b^2}\right) + \varepsilon^2\left(\frac{n^2\,x^2}{a^4} + \frac{y^2}{a^2\,b^2}\right) = 0;$$

and if $n = 0$, this becomes

$$(88)\ \left(\frac{x^2}{a^2}+\frac{y^2}{b^2}\right)^2-\frac{x^2}{a^2}-\left(1-\frac{\varepsilon^2}{a^2}\right)\frac{y^2}{b^2}=0;$$

the equation of the median section.

In (88) let $y = b\sqrt{1-\frac{\varepsilon^2}{a^2}}$ = height above X Z of lowest point of crown of arch = ordinate of median section where $x = 0$.

$$\therefore\left(\frac{x^2}{a^2}+\left(1-\frac{\varepsilon^2}{a^2}\right)\right)^2-\frac{x^2}{a^2}-\left(1-\frac{\varepsilon^2}{a^2}\right)^2=0;$$

whence by reduction

$$(89)\qquad x = \pm\sqrt{2\,\varepsilon^2 - a^2}.$$

This equation gives the x co-ordinates of the points in which a tangent to the median section at the extremity of its minor axis cuts the curve. In order that the arch may stand, these points must be imaginary.

In (89) when $\varepsilon > a\sqrt{\frac{1}{2}} > 0.7071\,a$, x is real;
" $\varepsilon = a\sqrt{\frac{1}{2}} = 0.7071\,a$, $x = 0$;
" $\varepsilon < a\sqrt{\frac{1}{2}} < 0.7071\,a$, x is imaginary.

The third of these cases is therefore the condition of stability.

The same result may be obtained by differentiating (88), placing $\frac{dy}{dx} = 0$, and making the condition that there shall be only one value of x for which y is a maximum.

In equation (86) if $\varepsilon = 0$, we have

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1,$$

a cylinder whose axis is O Z.

If $\varepsilon = a$, by transposing and extracting square root

$$\delta\left(\frac{x^2}{a^2} + \frac{y^2}{b^2}\right) - \frac{x\,z}{a} = \pm\,\frac{\delta\,x}{a},$$

the equation of two cones tangent to each other along the axis of z.

The equations of the c j s's can be found without difficulty, but they contain so many constants and are so complex as to be of no practical utility. The character of the arch as regards stability and tendency to sliding on the coursing joints, can be easily seen by examination of Fig. 3 and comparing it with Figs. 1 and 2. It will be noticed that the vertical

projection of each element takes a direction between those of the normals to the elliptical directrices at the points where it cuts them; therefore at some point between these it must coincide with the vertical projection of the normal to the section at that point by the heading plane through it. It follows that at this point the element will be perpendicular to the direction which has been assumed to be that of the pressure, and from the manner of its construction the c j s will be also normal to this direction. At the crown this point is midway between the faces of the arch, and as we approach the springing plane it moves toward the points A and C. The curve Λ U $\Im$ is cut from the c j s, R S *a c* by a horizontal plane through the point U, and the portion of it from U toward $\Im$ which would lie upon the coursing joint would evidently be nearly perpendicular to the direction of pressure. The curve η ν ξ is cut from the coursing joint surface through the element M N, and the portion which is upon the voussoir is almost

exactly perpendicular to the P F. $\mu_1 \gamma_1 \xi_1$ is cut from the surface of the lower face of the same course M Q. $\pi \rho \varsigma$ is the curve cut from the c j s through the first c j c on that side by a vertical plane perpendicular to the P F through B. It varies but slightly in the distance $\pi \varsigma$ from a right line. $\pi_1 \rho_1 \varsigma_1$ is a similar curve cut by a plane through L. The first one or two c j s's from the springing plane vary so slightly from a plane in the portion included between the inner and outer surfaces of the arch that they might well enough be made *exactly* plane when the number of courses is large.

This method of constructing the arch gives results therefore, as regards tendency to sliding in the coursing joints, *intermediate* between those found in the two methods previously considered, but approaching far more nearly to those obtained in the logarithmic method; that is, the c j s's are nearly normal to the direction of pressure.

An arch may also be constructed with the cow's horn soffit and *plane* coursing

joints as follows: On any element, as M N, take points midway between the heading planes, and at these points draw normals to the surface; through these normals and the element pass planes which will form the c j s's. The coursing joint will then be cut in a series of steps, and a portion of the voussoirs will have a triangular vertical face midway between the two ends. If the Ex s be also cut in steps, the voussoirs will have all their faces plane except the soffit, and all their edges straight lines except the intersections of the heading planes with the soffit. The construction of the drawings and cutting of the stones would thus be comparatively easy.

What was said in treating of the logarithmic method with regard to the limit of obliquity by reason of the edges of the voussoirs becoming too sharp where α is less than 60°, applies equally well to this method of construction. In this case, however, as in that, *segmental* arches can be built in which $\alpha < 60°$. Equation (51′) could be used to ascertain

approximately the allowable span for a given radius and obliquity when the semi-axes of the elliptical directrices have the ratio to each other $\frac{b}{a} = \cos.\ \alpha$; that



is, such that if the soffit were cylindrical, its right section would be a circle.

If the curved directrices are circles, we may obtain an approximate result as follows, by supposing the soffit to be cylindrical.

Let the angle $P_1 V^h P^h = \Phi$,
" $P^v E D = \gamma$,
" $A B^h B^\circ = \alpha$,
the distance $C P^h = x_1$,
" $D P^v = y_1$,

and β = the angle between the P F and the tangent plane to the soffit (supposed cylindrical).

A $V^v B^\circ$ will then be a right section of the cylinder, and its equation will be, if $V^h P = r$,

$$\frac{x^2}{r^2 \sin^2 \alpha} + \frac{y^2}{r^2} = 1.$$

The equation of the tangent plane to the cylinder will then be

$$\frac{x\, x_1}{r^2 \sin^2 \alpha} + \frac{y\, y_1}{r^2} = 1$$

or $$y = \frac{r^2}{y_1} - \frac{x_1}{y_1 \sin^2 \alpha}\, x$$

$$\therefore \tan \gamma = \frac{x_1}{y_1 \sin^2 \alpha}, \text{ and}$$

$$\sin \gamma = \frac{x_1}{\sqrt{x_1^2 + y_1^2 \sin^4 \alpha}}.$$

But by (51) $\sin \gamma = \dfrac{\cos \beta}{\cos \alpha} = \dfrac{1}{2 \cos \alpha}$

if we let $\beta = 60°$.

$$\therefore \frac{x_1}{\sqrt{x_1^2 + y_1^2 \sin^4 \alpha}} = \frac{1}{2 \cos \alpha}$$

$$\therefore \quad 4 x^2 \cos^2 \alpha = x_1^2 + y_1^2 \sin^4 \alpha.$$

Dividing by x_1^2,

$$4 \cos^2 \alpha = 1 + \frac{y_1^2}{x_1^2} \sin^4 \alpha$$

We have tan. $\Phi = \dfrac{y_1}{x_1 \operatorname{cosec} \alpha}$, whence

$\dfrac{y_1^2}{x_1^2} = \tan^2 \Phi \operatorname{cosec}^2 \alpha.$

Substituting

$$4 \cos^2 \alpha - 1 = \tan^2 \Phi \sin^2 \alpha$$

$$\therefore \quad \tan \Phi = \frac{\sqrt{4 \cos^2 \alpha - 1}}{\sin \alpha} \text{ whence}$$

$$\cos \Phi = \frac{\tan \alpha}{\sqrt{3}}.$$

(90) Oblique span $= 2\,r\,\cos\,\Phi$

$$= \frac{2}{\sqrt{3}}\,r\,\tan\,\alpha = 2\,r.\,\frac{\tan\,\alpha}{\tan 60°}.$$

If $\alpha = 30°$, oblique span $= \frac{2}{3}\,r.$

If $\alpha = 45°$, oblique span $= \frac{2}{\sqrt{3}}\,r = 1.1547\,r$

In the cow's horn soffit this formula, as well as (51′), will make the diedral angles at the edges of the voussoirs in the first course slightly greater or less than 60°, according to their position in the course. The exact solution of the problem involves an equation of the 4th degree with four real roots.

COMPARISON ON THE THREE METHODS.

There is one advantage possessed by the helicoidal method over each of the others; viz., that it may be constructed of brick. This is owing to the fact that the successive c j c's are *parallel*, so that the voussoirs, except those at the ends of the courses, are all exactly alike, while in

the other methods each stone is different from the next one, though the *two halves* of the arch on each side of the key-stone are alike, so that any stone cut for one side will fit also in the corresponding place on the other side. The fact that the different voussoirs are alike in the helicoidal method, of course lessens the labor of preparing the drawings, and of making the necessary measurements. As regards the difficulty of *cuttiny* the stones, however, this method does not seem to have any serious advantage over the others even by the approximate method of cutting which has been mentioned, while if the coursing and heading joint faces were cut with exactness, as *helicoids*, the difficulty would be fully equal to if not greater than that by the other methods.

It may be considered an advantage as regards *appearance* that the quoin-stones should be all alike, or rather those faces of the quoin-stones which coincide with the faces of the arch. This, of course, is the case only with the helicoidal method.

It apqears to me, however, that the gradual decrease in the size of these faces from one side of the arch to the other would not be displeasing to the eye, when taken in connection with the direction of the c j c's which would make the *reason* for the decrease obvious. The real test, however, is of the relative value of the different methods would appear to be that of *security*. When this test is applied, the logarithmic and cow's horn methods both excel by far the helicoidal. It has been shown that in the last mentioned, when semi-circular, there is *always* a tendency to sliding on the coursing joints, both above and below a certain point; that is, the assumed direction of pressure is nowhere normal to the coursing joints except at a certain height above the springing plane equal to r sin. 39° 32′ 23″, and that near the springing plane this tendency to sliding increases rapidly with the obliquity up to $\alpha = 20°$ (about); while in the logarithmic method along each c j c this tendency is zero; that is, the assumed direction of pressure

is normal to the c j s at any point of the c j c, and in the cow's horn the tendency is small as compared with the helicoidal.

The logarithmic method, therefore, seems to approximate to theoretical perfection as regards security, is followed closely by the cow's horn, and at a great distance by the helicoidal.

The cow's horn soffit admits of plane coursing-joints, as has been shown, which are not feasible in the others, and thus possesses an advantage over them, if such an approximate construction be desirable. If *cheapness* be an important item to be considered, the last-mentioned method would seem to present most advantages, as avoiding almost entirely the use of curved surfaces, and at the same time reducing the sliding tendency to a small amount.

If the main thing to be considered is *security*, the logarithmic method must stand first.

CATALOGUE

OF THE

SCIENTIFIC PUBLICATIONS

OF

D. VAN NOSTRAND COMPANY,

23 MURRAY STREET AND 27 WARREN STREET, N. Y.

A. B. C. CODE. (See Clausen-Thue.)

ABBOTT (A. V.). The Electrical Transmission of Energy. A Manual for the Design of Electrical Circuits. Second edition, revised. Fully illustrated. 8vo, cloth..... $4 50

ABBOT (Gen'l HENRY L.). The Defence of the Seacoast of the United States. Lectures delivered before the U. S. Naval War College. 8vo, red cloth. 2 00

ADAMS (J. W.). Sewers and Drains for Populous Districts. Embracing Rules and Formulas for the dimensions and construction of works of Sanitary Engineers. Fifth edition. 8vo, cloth. 2 50

A1. CODE. (See Clausen-Thue.)

AIKMAN (C. M., Prof.). Manures and the Principles of Manuring. 8vo, cloth..... 2 50

ALEXANDER (J. H.). Universal Dictionary of Weights and Measures, Ancient and Modern, reduced to the Standards of the United States of America. New edition, enlarged. 8vo, cloth 3 50

ALEXANDER (S. A.). Broke Down: What Should I Do? A Ready Reference and Key to Locomotive Engineers and Firemen, Round House Machinists, Conductors. Train Hands and Inspectors. With 5 folding plates. 12mo, cloth..... 1 50

ALLEN (C F.). Tables for Earthwork Computation. 8vo, cloth 1 50

ANDERSON (J. W.). The Prospector's Hand-book; A Guide for the Prospector and Traveller in search of metal-bearing or other Valuable Minerals. Seventh edition, thoroughly revised and much enlarged. 8vo, cloth..... 1 50

ANDERSON (WILLIAM). On the Conversion of Heat into Work. A Practical Hand-book on Heat-Engines. Third edition. Illustrated. 12mo, cloth. 2 25

ANDES (LOUIS). Vegetable Fats and Oils; their Practical Preparation, Purification and Employment for various purposes. Their Properties. Adulteration and Examination. A Hand-book for Oil Manufacturers and Refiners, Candle, Soap and Lubricating Oil Manufacturers and the Oil and Fat Industry in general. Translated from the German. With 94 illustrations. 8vo, cloth..... 4 00

——— Animal Fats and Oils. Their Practical Production, Purification and Uses for a great variety of purposes, their Properties, Falsification and Examination. A Hand-book for Manufacturers of Oil and Fat Products, Soap and Candle Makers, Agriculturists, Tanners, etc. Translated by Charles Salter. With 62 illustrations. 8vo, cloth.....net 4 00

ARNOLD (Dr. R.). Ammonia and Ammonium Compounds. A Practical Manual for Manufacturers, Chemists, Gas Engineers and Drysalters. Second edition. 12mo, cloth..... 2 00

ARNOLD (E.). Armature Windings of Direct Current Dynamos. Extension and Application of a General Winding Rule. Translated from the original German by Francis B. DeGress, M. E. With numerous illustrations.....(In Press.)

ATKINSON (PHILIP). The Elements of Electric Lighting, including Electric Generation, Measurement, Storage, and Distribution. Ninth edition. Fully revised and new matter added. Illustrated. 12mo, cloth..... 1 50

——— The Elements of Dynamic Electricity and Magnetism. Third edition. 120 illustrations. 12mo, cloth..... 2 00

ATKINSON (PHILIP). Power Transmitted by Electricity and its Application by the Electric Motor, including Electric Railway Construction. New edition, thoroughly revised, and much new matter added. Illustrated 12mo, cloth.... ..... 2 00

—— Elements of Static Electricity, with full description of the Holtz and Topler Machines, and their mode of operating. Illustrated. 12mo, cloth 1 50

AUCHINCLOSS (W. S.). Link and Valve Motions Simplified. Illustrated with 29 woodcuts and 20 lithographic plates, together with a Travel Scale, and numerous useful tables, Thirteenth edition, revised. 8vo, cloth..... 2 00

AXON (W. E. A.). The Mechanic's Friend. A Collection of Receipts and Practical Suggestions. 12mo, cloth 1 50

BACON (F. W.). A Treatise on the Richards, Steam-Engine Indicator, with directions for its use. By Charles T. Porter. Revised, with notes and large additions as developed by American practice; with an appendix containing useful formulæ and rules for engineers. Illustrated. Fourth edition. 12mo, cloth 1 00

BADT (F. B.). New Dynamo Tender's Hand book. With 140 illustrations. 18mo, cloth... ..... 1 00

—— Bell Hangers' Hand-book. With 97 illustrations. Second edition. 18mo, cloth..... ..... 1 00

—— Incandescent Wiring Hand-book. With 35 illustrations and five tables. Fifth edition. 18mo, cloth. 1 00

—— Electric Transmission Hand-book. With 22 illustrations and 27 tables. 18mo, cloth 1 00

BALE (M. P.). Pumps and Pumping. A Hand-book for Pump Users. 12mo, cloth..... ..... 1 00

BARBA (J.). The Use of Steel for Constructive Purposes. Method of Working, Applying, and Testing Plates and Bars With a Preface by A. L Holley, C. E. 12mo, cloth 1 50

BARKER (ARTHUR H.). Graphic Methods of Engine Design. Including a Graphical Treatment of the Balancing of Engines. 12mo, cloth.... 1 50

BARNARD (F. A. P.). Report on Machinery and Processes of the Industrial Arts and Apparatus of the Exact Sciences at the Paris Universal Exposition, 1867. 152 illustrations and 8 folding plates. 8vo, cloth 5 00

BARNARD (JOHN H.). The Naval Militiaman's Guide. Full leather, pocket form. 1 25

BARWISE (SIDNEY, M. D., London). The Purification of Sewage. Being a brief account of the Scientific Principles of Sewage Purification and their Practical Application. 12mo, cloth. Illustrated. 2 00

BAUMEISTER (R.). The Cleaning and Sewage of Cities. Adapted from the German with permission of the author. By J. M. Goodell, C. E. Second edition, revised and corrected, together with an additional appendix. 8vo, cloth. Illustrated..... 2 00

BEAUMONT (ROBERT). Color in Woven Design. With 32 Colored Plates and numerous original illustrations. Large 12mo..... 7 50

BEAUMONT, W. and DUGALD CLERK. Autocars and Horseless Carriages..... .....(In Press.)

BECKWITH (ARTHUR). Pottery. Observations on the Materials and Manufacture of Terra-Cotta, Stoneware, Fire-Brick, Porcelain, Earthenware, Brick, Majolica, and Encaustic Tiles. 8vo, paper. Second edition..... 60

BERNTHSEN (A.). A Text-Book of Organic Chemistry. Translated by George M'Gowan, Ph. D. Third English edition. Revised and extended by author and translator. Illustrated. 12mo, cloth..... 2 50

BERTIN (L. E.). Marine Boilers: Their Construction and Working, dealing more especially with Tubulous Boilers. Translated by Leslie S. Robertson. Upward of 250 illustrations. Preface by Sir William White. 8vo, cloth. Illustrated..... 7 50

BIGGS (C. H. W.). First Principles of Electricity and Magnetism. Being an attempt to provide an Elementary Book for those intending to enter the profession of Electrical Engineering. Second edition. 12mo, cloth. Illustrated..... 2 00

BLAKE (W. P.). Report upon the Precious Metals. Being Statistical Notices of the principal Gold and Silver producing regions of the world, represented at the Paris Universal Exposition. 8vo, cloth..... 2 00

—— Ceramic Art. A Report on Pottery, Porcelain, Tiles, Terra-Cotta, and Brick. 8vo, cloth..... 2 00

BLAKESLEY (T. H.). Alternating Currents of Electricity. For the use of Students and Engineers. Third edition, enlarged. 12mo, cloth..... 1 50

BLOUNT (BERTRAM). Electro-Metallurgy ..... (In Press.)

BLYTH (A. WYNTER, M. R. C. S., F. C. S.). Foods: their Composition and Analysis. A Manual for the use of Analytical Chemists, with an Introductory Essay on the History of Adulterations, with numerous tables and illustrations. Fourth edition, revised and enlarged. 8vo, cloth 7 50

—— Poisons: their Effects and Detection. A Manual for the use of Analytical Chemists and Experts, with an Introductory Essay on the growth of Modern Toxicology. Third edition, revised and enlarged. 8vo, cloth..... 7 50

BODMER (G. R.). Hydraulic Motors; Turbines and Pressure Engines, for the use of Engineers, Manufacturers and Students. Second edition, revised and enlarged. With 204 illustrations. 12mo, cloth..... 5 00

BOILEAU (J. T.). A New and Complete Set of Traverse Tables Showing the Difference of Latitude and Departure of every minute of the Quadrant and to five places of decimals. 8vo, cloth. 5 00

BOTTONE (S. R.). Electrical Instrument Making for Amateurs. A Practical Hand-book. With 48 illustrations. Fifth edition, revised. 12mo, cloth..... 50

—— Electric Bells, and all about them. A Practical Book for Practical Men. With more than 100 illustrations. 12mo, cloth. Fourth edition, revised and enlarged..... 50

——The Dynamo: How Made and How Used. A Book for Amateurs. Eighth edition. 12mo, cloth... 1 00

BOTTONE (S. R.). Electro Motors: How Made and How Used. A Hand-book for Amateurs and Practical Men. Second edition. 12mo, cloth..... . 50

BONNEY (G. E.). The Electro-Platers' Hand-book. A Manual for Amateurs and Young Students on Electro-Metallurgy. 60 illustrations, 12mo, cloth.. 1 20

BOW (R. H.). A Treatise on Bracing. With its application to Bridges and other Structures of Wood or Iron. 156 illustrations. 8vo, cloth..... 1 50

BOWSER (Prof. E. A.). An Elementary Treatise on Analytic Geometry. Embracing Plane Geometry, and an Introduction to Geometry of three Dimensions. 12mo, cloth. Nineteenth edition..... 1 75

—— An Elementary Treatise on the Differential and Integral Calculus With numerous examples. 12mo, cloth. Sixteenth edition 2 25

—— An Elementary Treatise on Analytic Mechanics. With numerous examples. 12mo, cloth. Twelfth edition..... .... 3 00

—— An Elementary Treatise on Hydro-Mechanics. With numerous examples. 12mo, cloth Fifth edition.... ..... 2 50

—— A Treatise on Roofs and Bridges. With Numerous Ex rcises. Especially adapted for school use. 12mo, cloth. Illustrated ....net 2 25

—— Academic Algebra. Third edition. 12mo, cloth.. 1 25

—— College Algebra. Fourth edition. 12mo, cloth.. 1 75

—— Elements of Plane and Solid Geometry. 12mo, cloth. Second edition..... . 1 40

BOWIE (AUG J., Jun., M. E.). A Practical Treatise on Hydraulic Mining in California. With Description of the Use and Construction of Ditches, Flumes, Wrought-iron Pipes and Dams; Flow of Water on Heavy Grades, and its Applicability, under High Pressure, to Mining. Fifth edition. Small quarto, cloth. Illustrated..... ..... 5 00

BURGH (N. P.). Modern Marine Engineering, applied to Paddle and Screw Propulsion. Consisting of 36 colored plates, 259 practical woodcut illustrations,

and 403 pages of descriptive matter. The whole being an exposition of the present practice of James Watt & Co., J. & G. Rennie, R. Napier & Sons, and other celebrated firms. Thick quarto, half morocco. 10 00

BURT (W. A.). Key to the Solar Compass, and Surveyor's Companion. Comprising all the rules necessary for use in the field; also description of the Linear Surveys and Public Land System of the United States. Notes on the Barometer, Suggestions for an Outfit for a Survey of Four Months, etc. Fifth edition. Pocket-book form, tuck 2 50

CALDWELL, (G. C.), and A. A. BRENEMAN. Manual of Introductory Chemical Practice. For the use of Students in Colleges and Normal and High Schools. Fourth edition, revised and corrected. 8vo, cloth Illustrated..... 1 50

CAMPIN (FRANCIS). On the Construction of Iron Roofs. A theoretical and Practical Treatise, with wood cuts and Plates of Roofs recently executed. 8vo, cloth..... 2 00

CARTER (E. T.). Motive Power and Gearing for Electrical Machinery. A Treatise on the Theory and Practice of the Mechanical Equipment of Power Stations for Electric supply and for Electric Traction. 8vo, cloth. Illustrated..... 5 00

CHAMBER'S MATHEMATICAL TABLES, consisting of logarithms of Numbers 1 to 108,000, Trigonometrical, Nautical, and other tables. New edition. 8vo, cloth..... 1 75

CHAUVENET (Prof. W.). New Method of Correcting Lunar Distances, and Improved Method of Finding the Error and Rate of a Chronometer, by Equal Altitudes. 8vo, cloth 2 00

CHRISTIE (W. WALLACE). Chimney Design and Theory. A Book for Engineers and Architects, with numerous half-tone illustrations and plates of famous chimneys. 12mo, cloth..... 3 00

CHURCH (JOHN A.). Notes of a Metallurgical Journey in Europe. 8vo, cloth 2 00

CLARK D. (KINNEAR, C. E.). A Manual of Rules, Tables and Data for Mechanical Engineers. Based

on the most recent investigations. Illustrated with numerous diagrams. 1,012 pages. 8vo, cloth. Sixth edition 5 00
Half morocco 7 50

CLARK D. (KINNEAR, C. E.). Fuel: its Combustion and Economy, consisting of abridgements of Treatise on the Combustion of Coal. By C. W. Williams; and the Economy of Fuel, by T. S. Prideaux With extensive additions in recent practice in the Combustion and Economy of Fuel, Coal, Coke, Wood, Peat, Petroleum, etc. Fourth edition. 12mo, cloth..... 1 50

——— The Mechanical Engineer's Pocket-book of Tables, Formulæ, Rules and Data. A Handy Book of Reference for Daily Use in Engineering Practice. 16mo, morocco. Second edition..... 3 00

———Tramways, their Construction and Working, embracing a comprehensive history of the system, with accounts of the various modes of traction, a description of the varieties of rolling stock, and ample details of Cost and Working Expenses. Second edition. Re-written and greatly enlarged, with upwards of 400 illustrations. Thick 8vo. cloth. 9 00

——— The Steam Engine. A Treatise on Steam Engines and oilers; comprising the Principles and Practice of the Combustion of Fuel, the Economical Generation of Steam, the Construction of Steam Boilers, and the Principles, Construction and Performance of Steam Engines, Stationary, Portable, Locomotive and Marine, exemplified in Engines and Boilers of recent date. 1,300 figures in the text, and a series of folding plates drawn to scale. 2 vols. 8vo, cloth. 15 00

CLARK (JACOB M.). A new System of Laying Out Railway Turn-outs instantly, by inspection from Tables 12mo, leatherette..... 1 00

CLAUSEN-THU (W.). The A. B. C. Universal Commercial Electric Telegraphic Code; especially adapted for the use of Financiers, Merchants, Shipowners, Brokers, Agent, etc. Fourth edition. 8vo, cloth. 5 00

——— The A1 Universal Commercial Electric Telegraphic Code. Over 1,240 pp., and nearly 10,000 variations. 8vo, cloth. 7 50

CLEEMANN (THOS. M.). The Railroad Engineer's Practice. Being a Short but Complete Description of the Duties of the Young Engineer in the Preliminary and Location Surveys and in Construction. Fourth edition. Revised and enlarged. Illustrated. 12mo, cloth 1 50

CLERK (DUGALD). Auto-cars or Horseless Vehicles. About 300 pp, 60 illustrations..... .....(In Press.)

CLEVENGER (S. R.). A Treatise on the Method of Government Surveying as prescribed by the U. S. Congress and Commissioner of the General Land Office, with complete Mathematical, Astronomical and Practical Instructions for the use of the United States Surveyors in the field. 16mo, morocco..... 2 50

COFFIN (Prof. J. H. C.). Navigation and Nautical Astronomy. Prepared for the use of the U. S. Naval Academy. New Edition. Revised by Commander Charles Belknap. 52 woodcut illustrations. 12mo, cloth ..... net. 3 50

COLE (R. S., M. A.). A Treatise on Photographic Optics. Being an account of the Principles of Optics, so far as they apply to Photography. 12mo, cloth, 108 illustrations and folding plates..... 2 50

COLLINS (JAS. E.). The private Book of Useful Alloys, and Memoranda for Goldsmiths, Jewelers, etc. 18mo, cloth 50

CORNWALL (Prof. H. B.). Manual of Blow-pipe Analysis, Qualitative and Quantitative. With a Complete System of Descriptive Mineralogy. 8vo, cloth. With many illustrations..... 2 50

CRAIG (B. F.). Weights and Measures. An Account of the Decimal System, with Tables of Conversion for Commercial and Scientific Uses. Square 32mo, limp cloth 50

CROCKER (F. B.). Electric Lighting. A Practical Exposition of the Art, for use of Engineers, Students, and others interested in the Installation or Operation of Electrical Plants. Second edition. Revised. 8vo, cloth. Vol. 1. The Generating Plant 3 00
Vol. 2..... .....(In Press.)

CROCKER (F. B.), and S. S. WHEELER. The Practical Management of Dynamos and Motors. Fourth edition (eighth thousand). Revised and enlarged. With a special chapter by H. A. Foster. 12mo, cloth. Illustrated..... 1 00

CUMMING (JOHN INNÆUS, M. A.). Electricity treated Experimentally. For the use of Schools and Students. New edition. 12mo, cloth..... 1 50

DAVIES (E. H.). Machinery for Metalliferous Mines. A Practical Treatise for Mining Engineers, Metallurgists and Manufacturers. With upwards of 300 illustrations. 8vo, cloth..... 5 00

DAVIS (JOHN W., C. E.). Formulæ for the Calculation of Railroad Excavation and Embankment, and for finding Average Haul. Second edition. Octavo, half roan..... 1 50

DAY (CHARLES). The Indicator and its Diagrams. With Chapters on Engine and Boiler Testing; Including a Table of Piston Constants compiled by W. H. Fowler. 12mo, cloth. 125 illustrations..... 2 00

DERR (W. L.). Block Signal Operation. A Practical Manual. Oblong, cloth..... 1 50

DIXON (D. B.). The Machinist's and Steam Engineer's Practical Calculator. A Compilation of Useful Rules and Problems arithmetically solved, together with General Information applicable to Shop-Tools, Mill Gearing, Pulleys and Shafts, Steam-Boilers and Engines. Embracing valuable Tables and Instruction in Screw-cutting, Valve and Link Motion, etc. 16mo, full morocco, pocket form..... 1 25

DODD (GEO.). Dictionary of Manufactures, Mining, Machinery, and the Industrial Arts. 12mo, cloth ... 1 50

DORR (B. F.). The Surveyor's Guide and Pocket Table Book. 18mo, morocco flaps. Third edition... 2 00

DRAPER (C. H.). An Elementary Text Book of Light, Heat and Sound, with Numerous Examples. Fourth edition. 12mo, cloth. Illustrated..... 1 00

——— **Heat and the Principles of Thermo-Dynamics. With many illustrations and numerical examples.** 12mo, cloth..... 1 50

DUBOIS (A. J.). The New Method of Graphic Statics. With 60 illustrations. 8vo, cloth..... 1 50

EDDY (Prof. H. T.). Researches in Graphical Statics, embracing New Constructions in Graphical Statics, a New General Method in Graphical Statics, and the Theory of Internal Stress in Graphical Statics. 8vo, cloth..... 1 50

——— Maximum Stresses under Concentrated Loads. Treated graphically. Illustrated. 8vo, cloth..... 1 50

EISSLER (M.). The Metallurgy of Gold; a Practical Treatise on the Metallurgical Treatment of Gold-Bearing Ores, including the Processes of Concentration and Chlorination, and the Assaying, Melting and Refining of Gold. Fourth Edition, revised and greatly enlarged. 187 illustrations. 12mo, cloth.... 5 00

——— The Metallurgy of Silver; a Practical Treatise on the Amalgamation, Roasting and Lixivation of Silver Ores, including the Assaying, Melting and Refining of Silver Bullion. 124 illustrations. Second edition, enlarged 12mo, cloth..... 4 00

——— The Metallurgy of Argentiferous Lead; a Practical Treatise on the Smelting of Silver-Lead Ores and the Refining of Lead Bullion. Including Reports on Various Smelting Establishments and Descriptions of Modern Smelting Furnaces and Plants in Europe and America. With 183 illustrations. 8vo, cloth..... 5 00

——— Cyanide Process for the Extraction of Gold and its Practical Application on the Witwatersrand Gold Fields in South Africa. Second edition. Enlarged 8vo, cloth. Illustrations and folding plates..... 3 00

——— A Hand-book on Modern Explosives, being a Practical Treatise on the Manufacture and use of Dynamite, Gun Cotton, Nitro-Glycerine and other Explosive Compounds, including the manufacture of Collodion-Cotton, with chapters on explosives in practical application. Second edition, enlarged with 150 illustrations. 12mo, cloth..... 5 00

ELIOT (C. W.), and STORER (F. H.). A compendious Manual of Qualitative Chemical Analysis. Revised with the co-operation of the authors, by Prof. William R. Nichols. Illustrated. Nineteenth edition, newly revised by Prof. W. B. Lindsay. 12mo, cloth..... 1 25

ELLIOT (Maj. GEO. H.). European Light-House Systems. Being a Report of a Tour of Inspection made in 1873. 51 engravings and 21 woodcuts. 8vo, cloth..... 5 00

ELLISON (LEWIS M.). Practical Application of the Indicator. With reference to the adjustment of Valve Gear on all styles of Engines. Second edition, revised. 8vo, cloth, 100 illustrations..... 2 00

EVERETT (J. D.). Elementary Text-Book of Physics. Illustrated. Seventh edition. 12mo, cloth 1 50

EWING (Prof. A. J.). The Magnetic Induction in Iron and other metals 159 illustrations. 8vo, cloth 4 00

FANNING (J. T.). A Practical Treatise on Hydraulic and Water-Supply Engineering. Relating to the Hydrology, Hydro-dynamics, and Practical Construction of Water-Works in North America. 180 illustrations 8vo, cloth. Fourteenth edition, revised, enlarged, and new tables and illustrations added. 650 pages..... 5 00

FISH (J. C. L.). Lettering of Working Drawings. Thirteen plates, with descriptive text. Oblong, 9x12½, boards..... 1 00

FISKE (Lieut. BRADLEY A., U. S. N.). Electricity in Theory and Practice; or, The Elements of Electrical Engineering Eighth edition. 8vo, cloth 2 50

FISHER (H. K. C. and DARBY, W. C.), Students' Guide to Submarine Cable Testing. 8vo, cloth..... 2 50

FISHER (W. C.). The Potentiometer and its Adjuncts 8vo, cloth 2 25

FLEISCHMANN (W.). The Book of the Dairy. A Manual of the Science and Practice of Dairy Work. Translated from the German, by C. M. Aikman and R. Patrick Wright. 8vo, cloth..... 4 00

FLEMING (Prof. J. A.). The Alternate Current Transformer in Theory and Practice. Vol. 1—The Induction of Electric Currents; 611 pages. New edition. Illustrated. 8vo, cloth 5 00
Vol. 2. The Utilization of Induced Currents. Illustrated. 8vo, cloth..... 5 00

—— Electric Lamps and Electric Lighting. Being a course of four lectures delivered at the Royal Institution, April-May, 1894. 8vo, cloth, fully illustrated 3 00

FLEMING (Prof. J. A.). Electrical Laboratory Notes and Forms, Elementary and advanced. 4to, cloth, illustrated..... 5 00

FOLEY (NELSON), and THOS. PRAY, Jr. The Mechanical Engineers' Reference Book for Machine and Boiler Construction, in 2 parts. Part 1 General Engineering Data. Part 2—Boiler Construction. With fifty-one plates and numerous illustrations, specially drawn for this work. Folio, half mor.....25 00

FORNEY (MATTHIAS N.). Catechism of the Locomotive. Second edition, revised and enlarged. Forty-sixth thousand. 8vo, cloth 3 50

FOSTER (Gen. J. G., U. S. A.). Submarine Blasting in Boston Harbor, Massachusetts. Removal of Tower and Corwin Rocks. Illustrated with 7 plates. 4to, cloth..... 3 50

FOSTER (H. A.). Electrical Engineers' Pocket Book. 1000 pages with the collaboration of Eminent Specialists. .....(in press)

FOSTER (JAMES). Treatise on the Evaporation on Saccharine, Chemical and other Liquids by the Multiple System in Vacuum and Open Air. Second edition. Diagrams and large plates. 8vo, cloth.... 7 50

FOWLER. Mechanical Engineers' Pocket Book for 1900..... 1 00

FOX (WM.), and C. W. THOMAS, M. E. A Practical Course in Mechanical Drawing. 12mo cloth with plates..... 1 25

FRANCIS (JAS. B., C. E.). Lowell Hydraulic Experiments. Being a selection from experiments on Hydraulic Motors, on the Flow of Water over Weirs, in open Canals of uniform rectangular section, and through submerged Orifices and diverging Tubes. Made at Lowell, Mass. Fourth edition, revised and enlarged, with many new experiments, and illustrated with 23 copper plate engravings 4to, cloth 15 00

FROST (GEO. H.). Engineer's Field Book. By C. S. Cross. To which are added seven chapters on Railroad Location and Construction. Fourth edition. 12mo, cloth..... 1 00

FULLER (GEORGE W.). Report on the Investigations into the Purification of the Ohio River Water at Louisville, Kentucky, made to the President and Directors of the Louisville Water Company. Published under agreement with the Directors. 4to, cloth. 8 full page plates.....net 10 00

GEIPEL (WM.), and KILGOUR, (M. H.) A Pocketbook of Electrical Engineering Formula. Illustrated. 18mo, morocco..... 3 00
Large paper edition, wide margins. 8vo, morocco, gilt edges..... 5 00

GERBER (NICHOLAS). Chemical and Physical Analysis of Milk, Condensed Milk and Infant's Milk-Food. 8vo, cloth..... 1 25

GIBBS (WILLIAM F.). Lighting by Acetylene, Generators. Burners and Electric Furnaces. With 66 illustrations. Second edition revised. 12mo, cloth.. 1 50

GILLMORE (GEN. Q. A.). Treatise on Limes, Hydraulic Cements, and Mortars. Papers on Practical Engineering, United States Engineer Department, No 9, containing Reports of numerous Experiments conducted in New York City during the years of 1858 to 1861, inclusive. With numerous illustrations. 8vo cloth..... 4 00

—— Practical Treatise on the Construction of Roads, Streets, and Pavements, with 70 illustrations. 12mo, cloth..... 2 00

—— Report on Strength of Building Stones in the United States, etc. 8vo, illustrated cloth..... 1 00

GOLDING (HENRY A.). The Theta-Phi Diagram. Practically applied to Steam, Gas, Oil and Air Engines. 12mo, cloth. Illustrated.....net 1 25

GOODEVE (T. M.). A Text-Book on the Steam Engine. With a Supplement on Gas-Engines. Twelfth Edition, enlarged. 143 illustrations. 12mo, cloth... 2 00

GORDON (J. E. H.). School Electricity. Illustrations. 12mo, cloth..... 2 00

GORE (G., F. R. S.). The Art of Electrolytic Separation of Metals, etc. (Theoretical and Practical.) Illustrated. 8vo, cloth..... 3 50

—— Electro Chemistry Inorganic. Third Edition. 8vo, cloth..... 80

GOULD (E. SHERMAN). The Arithmetic of the Steam Engine. 8vo, cloth..... 1 00

GRIFFITHS (A. D., Ph. D.). A Treatise on Manures, or the Philosophy of Manuring. A Practical Hand-Book for the Agriculturist, Manufacturer and Student. 12mo, cloth..... 3 00

GROVER (FREDERICK). Practical Treatise on Modern Gas and Oil Engines. 8vo, cloth. Illustrated 2 00

GURDEN (RICHARD LLOYD). Traverse Tables: computed to 4 places Decimals for every ° of angle up to 100 of Distance. For the use of Surveyors and Engineers. New Edition. Folio, half morocco. .. 7 50

GUY ARTHUR (F.). Electric Light and Power, giving the Result of Practical Experience in Central Station Work. 8vo, cloth. Illustrated.. .... 2 50

HAEDER (HERMAN C. E.). A Hand book on the Steam Engine. With especial reference to small and medium sized engines. English edition re-edited by the author from the second German edition. and translated with considerable additions and alterations by H. H. P. Powels. 12mo, cloth. Nearly 1100 illustrations.... .... 3 00

HALL (WM. S. Prof.). Elements of the Differential and Integral Calculus. Second edition. 8vo, cloth. Illustrated..... .....net 2 25

HALSEY (F. A.). Slide Valve Gears; an Explanation of the action and Construction of Plain and Cut-off Slide Valves. Illustrated. 12mo, cloth. Sixth edition. 1 50

——— The Use of the Slide Rule. Illustrated with diagrams and folding plates. 16mo, boards..... 50

HAMILTON (W. G.). Useful Information for Railway Men. Tenth Edition, revised and enlarged. 562 pages, pocket form. Morocco, gilt..... 2 00

HANCOCK (HERBERT). Text Book of Mechanics and Hydrostatics, with over 500 diagrams. 8vo, cloth 1 75

HARRISON (W. B.). The Mechanics' Tool Book. With Practical Rules and Suggestions for use of Machinists, Iron-Workers, and others. Illustrated with 44 engravings. 12mo, cloth..... .. 1 50

HASKINS (C. H.). The Galvanometer and its Uses. A Manual for Electricians and Students. Fourth edition. 12mo, cloth 1 50

HAWKE (WILLIAM H.). The Premier Cipher Telegraphic Code Containing 100,000 Words and Phrases. The most complete and most useful general code yet published. 4to, cloth 5 00

—— 100,000 Words; Supplement to the Premier Code. All the words are selected from the official vocabulary. Oblong quarto, cloth 4 20

HAWKINS (C. C.) and WALLIS (F.). The Dynamo; its Theory, Design and Manufacture. 190 illustrations, 12mo, cloth 3 00

HAY (ALFRED). Principles of Alternate-Current Working 12mo, cloth, illustrated 2 00

HEAP (Major D. P., U. S. A.). Electrical Appliances of the Present Day. Report of the Paris Electrical Exposition of 1881 250 illustrations. 8vo, cloth..... 2 00

HEAVISIDE (OLIVER). Electromagnetic Theory. 8vo, cloth, two volumes each 5 00

HENRICI (OLAUS). Skeleton Structures. Applied to the Building of Steel and Iron Bridges. Illustrated 1 50

HERRMANN (GUSTAV). The Graphical Statics of Mechanism. A Guide for the Use of Machinists, Architects, and Engineers; and also a Text-book for Technical Schools. Translated and annotated by A. P. Smith, M. E. 12mo, cloth, 7 folding plates. Third Edition 2 00

HERMANN (FELIX). Painting on Glass and Porcelain and Enamel Painting. On the Basis of Personal Practical Experience of the Condition of the Art up to date Translated by Charles Salter. Second greatly enlarged edition. 8vo, cloth, Illustrations, net 3 50

HEWSON (WM.). Principles and Practice of Embanking Lands from River Floods, as applied to the Levees of the Mississippi. 8vo, cloth..... 2 00

HILL (JOHN W.). The Purification of Public Water Supplies. Illustrated with valuable Tables, Diagrams and Cuts 8vo, cloth, 304 pages..... 3 00

—— The Interpretation of Water Analyses. (In Press)

HOBBS (W. R. P.). The Arithmetic of Electrical Measurements, with numerous examples. Fully Worked. 12mo, cloth ..... .50

HOFF (WM. B., Com. U. S. Navy). The Avoidance of Collisions at Sea. 18mo, morocco ..... .75

HOLLEY (ALEXANDER L.). Railway Practice. American and European Railway practice in the Economical Generation of Steam. 77 lithographed plates. Folio, cloth 12 00

HOLMES (A. BROMLEY). The Electric Light Popularly Explained. Fifth Edition Illustrated. 12mo, paper.... ..... .40

HOPKINS (NEVIL M.). Model Engines and small Boats. New Methods of Engine and Boiler Making with a chapter on Elementary Ship Design and Construction. 12mo, cloth 1 25

HOSPITALIER (E.). Polyphased Alternating Currents. Illustrated. 8vo, cloth 1 40

HOWARD (C. R.). Earthwork Mensuration on the Basis of the Prismoidal Formulae. Containing Simple and Labor-saving Methods of obtaining Prismoidal Contents directly from End Areas. Illustrated by Examples and accompanied by Plain Rules for Practical Uses Illustrated. 8vo, cloth..... 1 50

HUMBER (WILLIAM, C. E.). A Handy Book for the Calculation of Strains in Girders and Similar Structures, and their Strength; Consisting of Formulae and Corresponding Diagrams, with numerous details for practical application, etc. Fourth Edition. 12mo, cloth 2 50

HURST (GEORGE H.). Colour: A Hand-book of the Theory of Colour. Containing ten coloured plates and 72 diagrams. 8vo, cloth. Illustrated. Price... 2 50

—— Lubricating Oils, Fats and Greases. Their Origin, Preparation, Properties, Uses and Analysis. 313 pages, with 65 illustrations 8vo, cloth... ..... 3 00

—— Soaps; A Practical Manual of the Manufacture of Domestic Toilet and other Soaps. Illustrated with 66 Engravings. 8vo, cloth..... 5 00

HUTCHINSON (W. B.). Patents and How to Make Mo ey out of Them. Member of New York Bar. 12mo, cloth. New York, 1899 ..... 1 25

HUTTON (W. S.). Steam Boiler Construction. A Practical Hand-book for Engineers, Boiler Makers and Steam Users. Containing a large collection of rules and data relating to recent practice in the design, construction, and working of all kinds of stationary, locomotive and marine steam boilers. With upwards of 500 illustrations. Third edition. Carefully revised and much enlarged. 8vo, cloth... 6 00

—— Practica Engineer's Hand-book, Comprising a treatise on Modern Engines and Boilers, Marine, Locomotive and Stationary. Fourth edition. Carefully revised with additions. With upwards of 570 illustrations. 8vo, cloth..... 7 00

—— The Works' Manager's Hand-book of Modern Rules, Tables, and Data for Civil and Mechanical Engineers. Millwrights and Boiler Makers, etc., etc. With upwards of 150 illustrations. Fifth edition. Carefully revised, with additions. 8vo, cloth..... 6 00

INNES (CHARLES H.). Problems in Machine Design. For the Use of Students, Draughtsmen and others. 12mo, cloth..... 1 50

—— Centrifugal Pumps, Turbines and Water Motors. Including the Theory and Practice of Hydraulics. 12mo, cloth..... 1 50

ISHERWOOD (B. F.). Engineering Precedents for Steam Machinery. Arranged in the most practical and useful manner for Engineers. With illustrations. 2 vols. in 1. 8vo, cloth..... 2 50

JAMESON (CHARLES D.). Portland Cement. Its Manufacture and Use. 8vo, cloth..... 1 50

JAMIESON (ANDREW C. E.). A Text-Book on Steam and Steam Engines. Specially arranged for the use of Science and Art, City and Guilds of London Institute, and other Engineering Students. Tenth edition. Illustrated. 12mo, cloth..... 3 00

—— Elementary Manual on Steam and the Steam Engine. Specially arranged for the use of First-Year Science and Art, City and Guilds of London Institute, and other Elementary Engineering Students. Third edition. 12mo, cloth 1 40

JANNETTAZ (EDWARD). A Guide to the Determination of Rocks: being an Introduction to Lithology. Translated from the French by G. W. Plympton, Professor of Physical Science at Brooklyn Polytechnic Institute. 12mo, cloth 1 50

JOHNSTON, Prof. J. F. W., and CAMERON, Sir CHAS. Elements of Agricultural Chemistry and Geology. Seventeenth edition. 12mo, cloth..... 2 60

JOYNSON (F. H.). The Metals used in Construction. Iron, Steel, Bessemer Metal, etc. Illustrated. 12mo, cloth 75

—— Designing and Construction of Machine Gearing. Illustrated. 8vo, cloth.. ..... 2 00

KANSAS CITY BRIDGE (THE.) With an Account of the Regimen of the Missouri River and a Description of the Methods used for Founding in that River. By O. Chanute, Chief Engineer, and George Morrison, Assistant Engineer. Illustrated with 5 lithographic views and 12 plates of plans. 4to, cloth... 6 00

KAPP (GISBERT C. E.). Electric Transmission of Energy and its Transformation, Subdivision, and Distribution. A Practical Hand-book. Fourth edition, revised. 12mo, cloth..... 3 50

—— Dynamos, Alternators and Transformers. 138 Illustrations. 12mo, cloth..... 4 00

KEMPE (H. R.). The Electrical Engineer's Pocket-Book of Modern Rules, Formulæ, Tables and Data. Illustrated. 32mo, mor. gilt..... 1 75

KENNELLY (A. E.). Theoretical Elements of Electro Dynamic Machinery. 8vo, cloth. 1 50

KILGOUR, M. H., SWAN, H., and RIGGS, C. H. W. Electrical Distribution; its Theory and Practice. 174 Illustrations. 12mo, cloth..... 4 00

KING (W. H.). Lessons and Practical Notes on Steam. The Steam Engine, Propellers, etc., for Young Marine Engineers, Students, and others. Revised by Chief Engineer J. W. King, United States Navy. Nineteenth edition, enlarged. 8vo, cloth.... 2 00

KINGDON (J. A.). Applied Magnetism. An introduction to the Design of Electromagnetic Apparatus. 8vo, cloth..... 3 00

KIRKALDY (WM. G.). Illustrations of David Kirkaldy's System of Mechanical Testing, as Orig nated and Carried On by him during a Quarter of a Century. Comprising a Large Selection of Tabulated Results, showing the Strength and other Properties of Materials used in Construction, with explanatory Text and Historical Sketch. Numerous engravings and 25 lithographed plates. 4to, cloth..... 20 00

KIRKWOOD (JAS. P.). Report on the Filtration of River Waters for the supply of Cities, as practised in Europe, made to the Board of Water Commissioners of the City of St. Louis. Illustrated by 30 double-plate engravings. 4to, cloth..... 7 50

LARRABEE (C. S.). Cipher and Secret Letter and Telegraphic Code, with Hog's Improvements. The most perfect Secret Code ever invented or discovered. Impossible to read without the key. 18mo, cloth..... 60

LAZELLE (H. M.). One Law in Nature. A New Corpuscular Theory comprehending Unity of Force, Identity of Matter, and its Multiple Atom Constitution, etc. 12mo, cloth..... 1 50

LEASK (A. RITCHIE). Breakdowns at Sea and How to Repair Them. With eighty-nine Illustrations. 8vo, cloth. Second edition..... 2 00

——— Triple and Quadruple Expansion Engines and Boilers and their Management. With fifty-nine illustrations. Third edition, revised. 12mo, cloth.. 2 00

——— Refrigerating Machinery: Its Principles and Management. With sixty-four illustrations. 12mo, cloth..... 2 00

LECKY (S. T. S.). "Wrinkles" in Practical Navigation. With 130 illustrations. 8vo, cloth. Ninth edition, revised..... 8 40

LEVY (C. L.). Electric Light Primer. A Simple and Comprehensive Digest of all of the most important facts connected with the running of the dynamo, and electric lights, with precautions for safety. For the use of persons whose duty it is to look after the plant. 8vo, paper..... 50

LIVACHE (ACH., Ingenieur Civil Des Mines). The Manufacture of Varnishes, Oil Crushing, Refining and Boiling and Kindred Industries. Translated from the French and greatly extended, by John Geddes McIntosh. 8vo, cloth. Illustrated.....net 5 00

LOCKE (ALFRED G., and CHARLES G.) A Practical Treatise on the Manufacture of Sulphuric Acid. With 77 Constructive Plates drawn to cale Measurements, and other Illustrations. Royal 8vo, cloth. 10 00

LOCKERT (LOUIS). Petroleum Motor-Cars. 12mo, cloth 1 50

LOCKWOOD (THOS. D.). Electricity, Magnetism, and Electro-Telegraphy. A Practical Guide for Students, Operators, and Inspectors. 8vo, cloth. Third edition..... 2 50

——— Electrical Measurement and the Galvanometer; its Construction and Uses. Second edition. 82 illustrations. 12mo, cloth..... 1 50

LODGE (OLIVER J.). Elementary Mechanics, including Hydrostatics and Pneumatics. Revised edition. 12mo, cloth..... 1 50

LORING (A. E.). A Hand-book of the Electro-Magnetic Telegraph. Paper boards..... 50
Cloth. 75
Morocco..... 1 00

LUCE (Com. S. B.). Text-Book of Seamanship. The Equipping and Handling of Vessels under Sail or Steam. For the use of the U. S. Naval Academy. Revised and enlarged edition, by Lt. Wm. S. Benson. 8vo, cloth..... 10 00

LUNGE (GEO.). A Theoretical and Practical Treatise on the Manufacture of Sulphuric Acid and Alkali with the Collateral Branches. Vol. I. Sulphuric Acid, Second edition, revised and enlarged. 342 illustrations. 8vo, cloth..... 15 00
Vol. II. Second edition, revised and enlarged. 8vo, cloth..... 16 80
Vol III. 8vo, cloth. New edition, 1896..... 15 00

LUNGE, (GEO.), and HURTER, F. The Alkali Maker's Pocket-Book. Tables and Analytical Methods for Manufacturers of Sulphuric Acid, Nitric Acid, Soda, Potash and Ammonia. Second edition. 12mo, cloth 3 00

LUQUER (LEA McILVAINE, Ph. D.). Minerals in Rock Sections. The Practical Method of Identifying Minerals in Rock Sections with the microscope. Especially arranged for Students in Technical and Scientific Schools. 8vo. cloth. Illustrated..net 1 50

MACCORD (Prof. C. W.). A Practical Treatise on the Slide-Valve by Eccentrics, examining by methods the action of the Eccentric upon the Slide-Valve, and explaining the practical processes of laying out the movements adapting the Valve for its various duties in the Steam Engine. Second edition. Illustrated. 4to, cloth..... 2 50

MAGUIRE (Capt. EDWARD, U. S. A.). The Attack and Defence of Coast Fortifications. With Maps and Numerous Illustrations. 8vo, cloth..... 2 50

MAGUIRE (WM. R.). Domestic Sanitary Drainage and Plumbing Lectures on Practical Sanitation. 332 illustrations. 8vo..... 4 00

MARKS (EDWARD C. R.). Mechanical Engineering Materials: their Properties and Treatment in Construction. 12mo, cloth. Illustrated..... 60

—— Notes on the Construction of Cranes and Lifting Machinery. 12mo, cloth 1 00

MARKS (G. C.). Hydraulic Machinery Employed in the Concentration and Transmission of Power. 12mo, cloth 1 25

MAYER (WM.). American Telegraphy: Systems, Apparatus, Operation. 450 illustrations. 8vo, cloth. 3 50

MAYER (Prof. A. M.). Lecture Notes on Physics. 8vo, cloth..... ..... 2 00

McCULLOCH (Prof. R. S.). Elementary Treatise on the Mechanical Theory of Heat, and its application to Air and Steam Engines. 8vo, cloth..... 3 50

McNEILL (BEDFORD). McNeill's Code. Arranged to meet the requirements of Mining, Metallurgical and Civil Engineers, Directors of Mining, Smelting and other Companies, Bankers, Stock and Share Brokers, Solicitors, Accountants, Financiers, and General Merchants. Safety and Secrecy. 8vo, cloth. 6 00

MERRILL (Col. WM. E., U. S. A.). Iron Truss Bridges for Railroads The method of calcul ting strain in Trusses, with a careful comparison of the mo t pr minent Trusses, in reference t economy in combi ation, etc. Illustrated. 4to, cloth. Fourth Editi n 5 00

METAL TURNING. By a Foreman Pattern Maker. Illustrated with 81 engravi gs. 12mo, cloth..... 1 50

MINIFIE (WM.). Mechanical D awing. A Textbo k f Geometrical Draw ng for the use of Mechanics and Schools, in which he Definitions and Rules of Geo metry re fami iarly explained; the Practical Problems are arranged from the most simple to the more complex, and in their descr iption technicalities are avoid d as mu h as possible. With illustrations for Draw ng Pl ns Sec ions. and Elevations of Railways and Machinery; an Introduction to Isometric l Drawing, a d an Essay on Linea Perspective and Shadows Illustrated wit over 200 diagrams engraved on steel. Ninth t ousand. With a appendix on the Theory and A plication of Colors. 8vo, clot 4 00

—— Geom trical Drawing. Abridged from the Octavo edition, for the us of schools. Illus rated with 48 steel plates. Ninth edition. 12mo, cloth.... ..... 2 00

MODERN METEOROLOGY. A Series of Six Lectu es, d livered under the aus ices of the Meteorological Society in 1870. Illustrated. 12mo, cloth . 1 50

MOREING (C. A.), and NEAL (THOMAS). Te'egraphic Mining Co e Alpha etically arranged. Second edition. 8vo, cloth..... 8 40

MORRIS (E.). Easy Rules for the Measurement of Earthworks by means f the Prismoidal Formula. 8vo, cloth. Illustrated..... 1 50

MOSES (ALFRED J.), and PARSONS, C. L. Elements of Minera ogy. Crystallography and Blowpipe Analysis from a practical standpoint. Second thousand. 8vo, cloth. 366 illustrations..... .. net 2 00

MOSES (ALFRED J.). The Characters of Crystals. An Introduction to Physical Crystallography, co taining 321 Illustrations and Diagrams. 8vo, 211 pp. .... net 2 00

MOELLER (F. C. G.). Krupp's Steel Works. With 88 illustrations. By Felix Schmidt and Montan. Authorized Translation from the Ge man. 4to, cloth..... ....(In Press.)

MULLIN (JOSEPH P., M. E.). Modern Moulding and Pattern Making. A Practical Treatise upon Pattern Shop and Foundry Work; em racing the Moulding of Pulleys. Spur Gears, Worm Gears, Balance-Wheels, Stationary Engine and Locomotive Cylind rs, Globe Valves. Tool Work, Mining Machinery, Screw Propell-rs Pattern-Shop Machinery, and the latest improvements in English and American Cupolas; together with a large collection of original and careful y selected Rules and Tables for everyday use in the Drawing Office, Pat:ern-Shop and Foundry. 12mo, cloth. Illustrated..... 2 50

MUNRO (JOHN C. E.), and JAMIESON ANDREW C. E. A Pocket-book of Electrical Rules and Tables for the use of Electricians and Engineers. Thirteenth edition, revised and enlarged. With numerous diagrams. Pocket size. Leather.. 2 50

MURPHY (J. G., M. E.). Practical Mining. A Field Manual for Mining Engineers. With Hints for Investors in Mining Properties. 16mo, morocco tucks 1 00

NAQUET (A.). Legal Chemistry. A Guide to the Detection of Poisons, Falsification of Writings, Adulteration of Alimentary and Pharmaceutical Substances, Analysis of Ashes, and examination of Hair, Coins, Arms, and Stains, as applied to Chemical Jurisprudence. Translated from the French, by J. P. Battershall, Ph D., with a preface by C. F. Chandler, Ph. D., M. D., LL. D. 12mo, cloth..... 2 00

NASMITH (JOSEPH). The Student's Cotton Spinning. Third edition, revised and enlarged. 8vo, cloth. 622 pages. 250 Illustrations..... 3 00

NEWALL (JOHN W.). Plain Practical Directions for Drawing, S zing and Cutting Bevel-Gears, showing how the Teeth may be cut in a Plain Milling Machine or Gear Cutter so as to give them a correct shape from end to end; and showing how to get out all particulars for the Workshop without making any Drawings. Including a Full Set of Tables of Reference. Folding plates. 8vo, cloth. 1 50

NEWCOMB (EDWARD W.). Stepping Stones to Photography. 12mo, cloth. Illustrated. N. Y. 1899. (In Press.)

NEWLANDS (JAMES). The Carpenters' and Joiners' Assistant: being a Comprehensive Treatise on the Selection, Preparation and Strength of Materials, and the Mechanical Principles of Framing. Illustrated. Folio, half morocco..... 15 00

NIPHER (FRANCIS E., A. M.). Theory of Magnetic Measurements, with an appendix on the Method of Least Squares. 12mo, cloth 1 00

NOAD (HENRY M.). The Students' Text-Book of Electricity. A new edition, carefully revised. With an Introduction and additional chapters by W. H. Preece. With 471 illustrations. 12mo, cloth..... 4 00

NUGENT (E.). Treatise on Optics; or, Light and Sight theoretically and practically treated, with the application to Fine Art and Industrial Pursuits. With 103 illustrations. 12mo, cloth. 1 50

O'CONNOR (HENRY). The Gas Engineer's Pocket-Book. Comprising Tables, Notes and Memoranda; relating to the Manufacture, Distribut on and Use of Coal Gas and the Construction of Gas Works. 12mo, full leather, gilt edges..... 3 50

OUDIN (M. A.). Standard Polyphase Apparatus and Systems. Fully illustrated 3 00

PAGE (DAVID). The Earth's Crust, A Handy Outline of Geology. 16mo, cloth..... 75

PALAZ (A., ScD.). A Treatise on Industrial Photometry, with special application to Electric Lighting. Authorized translation from the French, by George W. Patterson, Jr. Second edition, revised. 8vo, cloth. Illustrated..... 4 00

PARSHALL (H. F.), and HOBART H. M. Armature Windings of Electric Machines. With 140 full page plates, 65 tables, and 165 pages of descriptive letter-press. 4to, cloth..... 7 50

PARSHALL (H. F.), and EVAN PARRY. Electrical Equipment of Tramways.....(In Press.)

PEIRCE (B.). System of Analytic Mechanics. 4to, cloth 10 00

—— Linear Associative Algebra. New edition, with addenda and notes, by C. L. Pierce. 4to, cloth 4 00

PERRINE (F. A. C., A. M., D. Sc.). Conductors for Electrical Distribution; their Manufacture and Materials, the Calculation of Circuits, Pole Line Construction, Underground Working and other Uses. (In Press.)

PERRY (JOHN). Applied Mechanics. A Treatise for the use of students who have time to work experimental, numerical and graphical exercises illustrating the subject. 8vo, cloth. 650 pages.,net 2 50

PHILLIPS (JOSHUA). Engineering Chemistry. A Practical Treatise for the use of Analytical Chemists, Engineers, Iron Masters, Iron Founders, students and others. Comprising methods of Analysis and Valuation of the principal materials used in Engineering works, with numerous Analyses, Examples and Suggestions. 314 illustrations. Second edition, revised and enlarged. 8vo, cloth..... 4 00

PICKWORTH (CHAS. N.). The Indicator Handbook. A Practical Manual for Engineers. Part I. The Indicator: Its Construction and Application. 81 illustrations. 12mo, cloth..... 1 50

—— The Slide Rule. A Practical Manual of Instruction for all Users of the Modern Type of Slide Rule, exhibiting the Application of the Instrument to the Everyday Work of the Engineer,— Civil, Mechanical and Electrical. 12mo, flexible cloth. Fifth edition. 80

PLANE TABLE (THE). Its Uses in Topographical Surveying. From the Papers of the United States Coast Survey. Illustrated. 8vo, cloth..... 2 00

PLANTE (GASTON). The Storage of Electrical Energy, and Researches in the Effects created by Currents, combining Quantity with High Tension. Translated from the French by Paul B. Elwell. 89 illustrations. 8vo..... 4 00

PLATTNER. Manual of Qualitative and Quantitative Analysis with the Blow Pipe. From the last German edition, revised and enlarged, by Prof. Th. Richter, of the Royal Saxon Mining Academy. Translated by Prof. H. B. Cornwall, assisted by John H. Caswell. Illustrated with 87 wood cuts and one lithographic plate. Seventh edition, revised. 560 pages. 8vo, cloth..... 5 00

PLYMPTON (Prof. GEO. W.). The Blow Pipe. A Guide to its use in the Determination of Salts and Minerals. Compiled from various sources. 12mo, cloth 1 50

—— The Aneroid Barometer: its Construction and Use. Compiled from several sources. Fourth edition. 16mo, boards. Illustrated... 50
Morocco..... ..... 1 00

POCKET LOGARITHMS, to Four Places of Decimals, including Logarithms of Numbers, and Logarithmic Sines and Tangents to Single Minutes. To which is added a Table of Natural Sines, Tangents, and Co-Tangents. 16mo, boards..... 50

POPE (F. L.). Modern Practice of the Electric Telegraph. A Technical Hand-book for Electricians, Managers and Operators. Fifteenth edition, rewritten and enlarged, and fully illustrated. 8vo, cloth. 1 50

POPPLEWELL (W. C.). Elementary Treatise on Heat and Heat Engines. Specially adapted for engineers and students of engineering. 12mo, cloth. Illustrated..... 3 00

POWLES (H. H.). Steam Boilers.....(In Press.)

PRAY (Jr., THOMAS). Twenty Years with the Indicator; being a Practical Text-Book for the Engineer or the Student, with no complex Formulæ. Illustrated. 8vo, cloth..... 2 50

—— Steam Tables and Engine Constant. Compiled from Regnault, Rankine and Dixon directly, making use of the exact records. 8vo, cloth..... 2 00

PRACTICAL IRON FOUNDING. By the Author of "Pattern Making," &c., &c. Illustrated with over one hundred engravings. 12mo, cloth..... 1 50

PREECE (W. H.). Electric Lamps .....(In Press.)

PREECE (W. H.), and STUBBS, A. T. Manual of Telephony. Illustrations and plates. 12mo, cloth. 4 50

PREMIER CODE. (See Hawk, Wm. H.)

PRESCOTT (Prof. A. B.). Organic Analysis. A Manual of the Descriptive and Analytical Chemistry of certain Carbon Compounds in Common Use: a Guide in the Qualitative and Quantitative Analysis of Organic Materials in Commercial and Pharma-

ceutical Assays, in the estimation of Impurities under Authorized Standards, and in Forensic Examinations for Poisons, with Directions for Elementary Organic Analysis. Fourth edition. 8vo, cloth..... 5 00

PRESCOTT (Prof. A. B.). Outlines of Proximate Organic Analysis, for the Identification, Separation, and Quantitative Determination of the more commonly occurring Organic Compounds. Fourth edition. 12mo, cloth 1 75

—— First Book in Qualitative Chemistry. Eighth edition. 12mo, cloth 1 50

—— and Otis Coe Johnson. Qualitative Chemical Analysis. A Guide in the Practical Study of Chemistry and in the work of Analysis. Fourth fully revised edition. With Descriptive Chemistry extended throughout..... 3 50

PRITCHARD (O. G.). The Manufacture of Electric Light Carbons. Illustrated. 8vo, paper 60

PULLEN (W. W. F.). Application of Graphic Methods to the Design of Structures. Specially prepared for the use of Engineers. 12mo, cloth. Illustrated net 2 50

PULSIFER (W. H.). Notes for a History of Lead. 8vo, cloth, gilt tops. 4 00

PYNCHON (Prof. T. R.). Introduction to Chemical Physics, designed for the use of Academies, Colleges, and High Schools. Illustrated with numerous engravings, and containing copious experiments with directions for preparing them. New edition, revised and enlarged, and illustrated by 269 illustrations on wood. 8vo, cloth..... ..... 3 00

RADFORD (Lieut. CYRUS S.). Hand-book on Naval Gunnery. Prepared by Authority of the Navy Department. For the use of U. S. Navy, U. S. Marine Corps and U. S. Naval Reserves. Revised and enlarged, with the assistance of Stokely Morgan, Lieut. U. S. N. Third edition. 12mo, flexible leather. 2 00

RAFTER (GEO. W.), and M. N. BAKER. Sewage Disposal in the United States. Illustrations and folding plates. Second edition. 8vo, cloth..... 6 00

RAM (GILBERT S.). The Incandescent Lamp and its Manufacture. 8vo, cloth.. ..... 3 00

RANDALL (J. E.). A Practical Treatise on the Incandescent Lamp. Illustrated. 16mo, cloth..... 50

RANDALL (P. M.). Quartz Operator's Hand-book. New edition, revised and enlarged, fully illustrated. 12mo, cloth..... 2 00

RANKINE (W. J. MACQUORN.) Applied Mechanics. Comprising the Principles of Statics and Cinematics, and Theory of Structures, Mechanism, and Machines. With numerous diagrams. Fifteenth edition. Thoroughly revised by W. J. Millar. 8vo, cloth..... 5 00

—— Civil Engineering. Comprising Engineering Surveys, Earthwork, Foundations, Masonry, Carpentry, Metal Work, Roads, Railways, Canals, Rivers, Water Works, Harbors, etc. With numerous tables and illustrations. Twentieth edition. Thoroughly revised by W. J. Millar. 8vo, cloth..... 6 50

—— Machinery and Millwork. Comprising the Geometry, Motions, Work, Strength, Construction, and Objects of Machines, etc. Illustrated with nearly 300 wood cuts. Seventh edition. Thoroughly revised by W. J. Millar. 8vo, cloth..... 5 00

—— The Steam Engine and other Prime Movers. With diagram of the Mechanical Properties of Steam-folding plates, numerous tables and illustrations. Thirteenth edition. Thoroughly revised by W. J. Millar. 8vo, cloth..... 5 00

—— Useful Rules and Tables for Engineers and Others. With appendix, tables, tests, and formulæ for the use of Electrical Engineers. Comprising Submarine Electrical Engineering, Electric Lighting, and Transmission of Power. By Andrew Jamieson, C. E., F. R. S. E. Seventh edition. Thoroughly revised by W. J. Millar. Crown 8vo, cloth..... 4 00

—— A Mechanical Text-Book. By Prof. Macquorn Rankine and E. F. Bamber, C. E. With numerous illustrations. Fourth edition. 8vo, cloth..... 3 50

RAPHAEL (F. C.). Localisation of Faults in Electric Light Mains. 8vo, cloth..... 2 00

RECKENZAUN (A.). Electric Traction on Railways and Tramways. 213 illustrations. 12mo, cloth..... 4 00

REED'S ENGINEERS' HAND-BOOK to the Local Marine Board Examinations for Certificates of Competency as First and Second Class Engineers. By W. H. Thorn. With the answers to the Elementary Questions. Illustrated by 247 diagrams and 36 large plates. Sixteenth edition, revised and enlarged. 8vo, cloth..... 5 00

—— Key to the Sixteenth Edition of Reed's Engineer's Hand-book to the Board of Trade Examinations for First and Second Class Engineers and containing the working of all the questions given in the examination papers By W. H Thorn. 8vo, cloth..... 3 00

—— Useful Hints to Sea-going Engineers, and How to Repair and Avoid "Break Downs;" also Appendices Containing Boiler Explosions, Useful Formulæ, etc. With 36 diagrams and 4 plates. Second edition, revised and enlarged. 12mo, cloth..... 1 40

—— Marine Boilers: A Treatise on the Causes and Prevention of their Priming, with Remarks on their General Management. Illustrated. 12mo, cloth... 2 00

REINHARDT (CHAS. W.). Lettering for Draftsmen, Engineers and Students. A Practical System of Free-hand Lettering for Working Drawings. Fourth thousand. Oblong, boards..... 1 00

RICE (J. M.)., and JOHNSON, W. W. On a New Method of obtaining the Differential of Functions, with especial reference to the Newtonian Conception of Rates or Velocities. 12mo, paper.... 50

RINGWALT (J. L.). Development of Transportation Systems in the United States, Comprising a Comprehensive Description of the leading features of advancement from the colonial era to the present time. With illustrations. Quarto, half morocco.. 7 50

RIPPER (WILLIAM). A Course of Instruction in Machine Drawing and Design for Technical Schools and Engineer Students. With 52 plates and numerous explanatory engravings. Folio, cloth..... 6 00

ROEBLING (J. A.). Long and Short Span Railway Bridges. Illustrated with large copperplate engravings of plans and views. Imperial folio, cloth..... 25 00

ROGERS (Prof. H. D.). The Geology of Pennsylvania. A Government Survey, with a General View of the Geology of the United States, essays on the Coal Formation and its Fossils, and a description of the Coal Fields of North America and Great Britain. Illustrated with plates and engravings in the text. 3 vols., 4to, cloth, with portfolio of maps. 15 00

ROSE (JOSHUA, M. E.). The Pattern Makers' Assistant. Embracing Lathe Work, Branch Work, Core Work, Sweep Work, and Practical Gear Constructions, the Preparation and Use of Tools, together with a large collection of useful and valuable Tables. Eighteenth edition. Illustrated with 250 engravings. 8vo, cloth..... 2 50

—— Key to Engines and Engine-running. A Practical Treatise upon the Management of Steam Engines and Boilers for the Use of Those who Desire to Pass an Examination to Take Charge of an Engine or Boiler. With numerous illustrations, and Instructions Upon Engineers' Calculations, Indicators, Diagrams, Engine Adjustments, and other Valuable Information necessary for Engineers and Firemen. 12mo, cloth..... 2 50

SABINE (ROBERT). History and Progress of the Electric Telegraph. With descriptions of some of the apparatus. Second edition, with additions. 12mo, cloth..... 1 25

SAELTZER (ALEX.). Treatise on Acoustics in connection with Ventilation. 12mo, cloth..... 1 00

SALOMONS (Sir DAVID, M. A.). Electric Light Installations. A Practical Hand-book. Eighth edition, revised and enlarged, with numerous illustrations. Vol. I. The management of Accumulators. 12mo, cloth..... 1 50
Vol. II., Apparatus, 296 illustrations. 12mo, cloth 2 25
Vol. III., Applications. 12mo, cloth..... 1 50

SANFORD (P. GERALD). Nitro-Explosives. A Practical Treatise concerning the Properties, Manufacture and Analysis of Nitrated Substances, including the Fulminates, Smokeless Powders and Celluloid. 8vo, cloth, 270 pages..... 3 00

SAUNNIER (CLAUDIUS). Watchmaker's Handbook. A Workshop Companion for those engaged

in Watchmaking and allied Mechanical Arts. Translated by J. Tripplin and E Rigg Second edition, revised with appendix. 12mo, cloth 8 50

SCHELLEN (Dr. H.). Magneto-Electric and Dynamo-Electric Machines: their Construction and Practical Application to Electric Lighting, and the Transmission of Power. Translated from the third German edition, by N. S. Keith and Percy Neymann, Ph. D. With very large additions and notes relating to American Machines, by N. S. Keith. Vol I., with 353 illustrations. Second edition 5 00

SCHUMANN (F.). A Manual of Heating and Ventilation in its Practical Application, for the use of Engineers and Architects. Embracing a series of Tables and Formulæ for dimensions of heating, flow and return pipes for steam and hot water boilers, flues, etc. 12mo, illustrated, full roan. 1 50

SCRIBNER (J. M.). Engineers' and Mechanics' Companion. Comprising United States Weights and Measures. Mensuration of Superfices and Solids, Tables of Squares and Cubes, Square and Cube Roots, Circumference and Areas of Circles, the Mechanical Powers, Centres of Gravity, Gravitation of Bodies, Pendulums, Specific Gravity of Bodies, Strength, Weight, and Crush of Materials, Water-Wheels, Hydrostatics, Hydraulics, Statics, Centres of Percussion and Gyration, Friction Heat, Tables of the Weight of Metals, Scantling, etc., Steam and the Steam Engine. Twentieth edition revised. 16mo, full morocco 1 50

SEATON (A. E.). A Manual of Marine Engineering. Comprising the Designing, Construction and Working of Marine Machinery. With numerous tables and illustrations reduced from Working Drawings. Fourteenth edition. Revised throughout, with an additional chapter on Water Tube Boilers. 8vo., cloth..... .... 6 00

—— **and ROUNTHWAITE (H. M.).** A Pocket-book of Marine Engineering Rules and Tables. For the use of Marine Engineers and Naval Architects, Designers, Draughtsmen, Superintendents, and all engaged in the design and construction of Marine Machinery, Naval and Mercantile. Fifth edition, revised and enlarged. Pocket size. Leather, with diagrams. Reprinting.

SEXTON (A. HUMBOLDT). Fuel and Refractory Materials. 8vo, cloth 2 00

SHIELDS (J. E.). Notes on Engineering Construction Embracing Discussions of the Principles involved, and Descriptions of the Material employed in Tunnelling, Bridging, Canal and Road Building, etc. 12mo, cloth 1 50

SHOCK (WM. H.). Steam Boilers: Their Design, Construction and Management. 4to, half morocco 15 00

SHREVE (S. H.). A Treatise on the Strength of Bridges and Roofs. Comprising the determination of Algebraic formulas for strains in Horizontal, Inclined or Rafter, Triangular, Bowstring, Lenticular, and other Trusses, from fixed and moving loads, with practical applications and examples, for the use of Students and Engineers. 87 woodcut illus. Fourth edition. 8vo, cloth 3 50

SHUNK (W. F.). The Field Engineer. A Handy Book of practice in the Survey, Location, and Truckwork of Railroads, containing a large collection of Rules and Tables, original and selected, applicable to both the Standard and Narrow Gauge, and prepared with special reference to the wants of the young Engineer. Eleventh edition, revised and enlarged. 12mo, morocco, tucks 2 50

SIMMS (F. W.). A Treatise on the Principles and Practice of Levelling. Showing its application to purposes of Railway Engineering, and the Construction of Roads, etc Revised and corrected, with the addition of Mr. Laws' Practical Examples for setting out Railway Curves. Illustrated. 8vo, cloth 2 50

IMMS (W. F.). Practical Tunnelling. Fourth edition, revised and greatly extended. With additional chapters illustrating recent practice by D. Kinnear Clark. With 36 plates and other illustrations. Imperial 8vo, cloth 12 00

SLATER (J. W.). Sewage Treatment, Purification, and Utilization. A Practical Manual for the Use of Corporations, Local Boards, Medical Officers of Health, Inspectors of Nuisances, Chemists, Manufacturers, Riparian Owners, Engineers, and Ratepayers. 12mo, cloth 2 25

SMITH (ISAAC W., C. E.). The Theory of Deflections and of Latitudes and Departures. With special applications to Curvilinear Surveys, for Alignments of Railway Tracks. Illustrated. 16mo, morocco, tucks.. .... 3 00

SNELL (ALBION T.). Electric Motive Power: The Transmission and Distribution of Electric Power by Continuous and Alternate Currents With a Section on the Applications of Electricity to Mining Work. Second edition. 8vo, cloth, illustrated..... 4 00

SPEYERS (CLARENCE L.). Text-Book of Physical Chemistry. 8vo, cloth.. .... 2 25

STAHL (A. W.), and A. T. WOODS. Elementary Mechanism. A Text-Book for Students of Mechanical Engineering. Fourth edition, enlarged. 12mo, cloth 2 00

STALEY (CADY), and PIERSON, GEO. S. The Separate System of Sewerage: its Theory and Construction. Third edition, revised. 8vo, cloth. With maps, plates and illustrations..... ..... 3 00

STEVENSON (DAVID, F.R.S.N.). The Principles and Practice of Canal and River Engineering. Revised by his sons David Alan Stevenson, B. Sc., F. R. S. E., and Charles Alexander Stevenson, B. Sc., F.R. S.E., Civil Engineer. Third edition, with 17 plates, 8vo, cloth..... ....10 00

——— The Design and Construction of Harbors, A Treatise on Maritime Engineering. Third edition with 24 plates, 8vo, cloth..... .. .. 9 00

STEWART (R. W.). A Text Book of Light, Adapted to the Requirements of the Intermediate Science and Preliminary Scientific Examinations of the University of London, and also for General Use, Numerous Diagrams and Examples. 12mo, cloth.. 1 00

STEWART (R. W.). A Text Book of Heat, Illustrated, 8vo, cloth..... .... 1 00

——— A Text Book of Magnetism and Electricity, 160 Illus. and Numerous Examples. 12mo, cloth..... 1 00

STILES (AMOS). Tables for Field Engineers. Designed for use in the field. Tables containing all the functions of a one degree curve, from which a corresponding one can be found for any required

degree. Also, Tables of Natural Sines and Tangents. 12mo, morocco, tucks 2 00

STILLMAN (PAUL). Steam Engine Indicator and the Improved Manometer Steam and Vacuum Gauges; their Utility and Application. New edition. 12mo, flexible cloth 1 00

STONE (General ROY). New Roads and Road Laws in the United States. 200 pages, with numerous illustrations. 12mo, cloth 1 00

STUART (C. B., U. S. N.). Lives and Works of Civil and Military Engineers of America. With 10 steel-plate engravings. 8vo, cloth 5 00

—— The Naval Dry Docks of the United States. Illustrated with 24 fine Engravings on Steel. Fourth edition. 4to, cloth 6 00

SWINTON (ALAN A. CAMPBELL). The Elementary Principle of Electric Lighting. Illustrated. 12mo, cloth 60

TEMPLETON (WM.). The Practical Mechanic's Work-shop Companion. Comprising a great variety of the most useful rules and formulæ in Mechanical Science, with numerous tables of practical data and calculated results facilitating mechanical operations. Revised and enlarged by W. S. Hutton. 12mo, morocco 2 00

THOM (CHAS.), and WILLIS H. JONES. Telegraphic Connections: embracing Recent Methods in Quadruplex Telegraphy. Oblong, 8vo, cloth. 20 full page plates, some colored 1 50

THOMPSON (EDWARD P., M. E.). How to Make Inventions; or Inventing as a Science and an Art. A Practical Guide for Inventors. Second edition. 8vo, boards 1 00

—— Roentgen Rays and Phenomena of the Anode and Cathode Principles, Applications and Theories. For Students, Teachers, Physicians, Photographers, Electricians and others. Assisted by Louis M. Pignolet, N. D. C. Hodges, and Ludwig Gutmann, E. E. With a Chapter on Generalizations, Arguments, Theories, Kindred Radiations and Phenomena. By Professor Wm. Anthony. 8vo, cloth. 50 Diagrams, 40 Half tones 1 50